# E2E

CSM E2E DS E 7 1

# Your Search for Proximity Sensors Starts with the World-leading Performance and Quality of the E2E

- Standard Sensors for detecting ferrous metals.
- Wide array of variations. Ideal for a variety of applications.
- Models with different frequencies are also available to prevent mutual interference.
- Superior environment resistance with standard cable made of oilresistant PVC and sensing surface made of material that resists cutting oil.
- Useful to help prevent disconnection.
   Cable protector provided as a standard feature.





Be sure to read *Safety Precautions* on page 27.




- \*1: No AC/DC 2-wire models or AC 2-wire M8 models are compliant.
- \*2: Attach three ferrite clamps to the cable of the E2E-X3□□ and E2E-X8MD□. (Refer to information on TDK catalog number ZCAT2035-0930A.)

## **Features**

#### 2-Wire Models

Pre-wired Models with Oil-resistant Reinforced PUR Cables Added to the Lineup and Easy Differentiation with Orange Head



Differentiation from standard models: Orange Head



Oil Resistance (Insulation service life): twice or three times that of oil-resistant vinyl chloride




Cable Flexibility: approximately twice that of cinyl chloride cables



More Flexibility at −40°C

# Lineup includes models with Smartclick pre-wired connectors for fast connection.



OMRON 1

# Lineup includes models with self-diagnostic output to provide notification of failures and unstable detection conditions, such as coil burnout.

• Contributes to preventive maintenance to keep the line from stopping.

# Reduced wiring, fewer resources, and low power consumption contribute to environmentalism.

- Wiring work and amount of copper wire used reduced to two thirds of that required for 3-wire models.
- Current consumption drastically reduced to less than 10% (when a DC 2-wire model is compared with a DC 3-wire model).

# **3-Wire Models**

# Lineup includes models with small diameter (3 dia., 4 dia., 5.4 dia., M5)

- All small-diameter models use sealed construction. Operation is stable even when the Sensor is mounted in a small space or embedded in metal.
- Bright indicators enable easily checking the installation condition.



# Wide range of ambient operating temperatures: -40°C to 85°C (M8 to M30 models)

- Wide range of ambient operating temperatures also for small-diameter models: -25°C to 70°C
- Suitable for low-temperature and high-temperature applications, which are troublesome for photoelectric sensors.

# Lineup includes models with flexible cable (4-dia. to M30 models)

• Reduced risk of disconnection in applications with moving parts.

# **Models Listed by E2E Type**

●: Standard Models, ▲: Different frequency, □: Self-diagnosis, ■: Different frequency and self-diagnosis, ---: Not listed

# 2-Wire Models


Purpose   Purp			stance			reinfo	sistant orced cable		(cable m		d cable a il-resistar			models		Pa	ige				
ACID   Shield and sheld	Power supply	Shielding	Size and sensing dis	Polarity	Operation mode	M12 pre-wired smartclick connector models	Pre-wired model with 2-m cable	M12 pre-wired smartclick connector models	Pre-wired model with standard 2-m cable	Pre-wired model with flexible 2-m cable	Pre-wired model with standard 5-m cable	M12 connector (IEC pin arrangement)	M12 standard pre-wired connector models	M8 connector	M12 connector (old pin arrangement)	Ordering Information	Dimensions refer- ence chart				
Part				Yes			•	•	•	•	•			•							
No			2 m	. 00			_		~		_	-		•		Refer to					
Shielded ed				Yes		_		•		•	_				_						
Shield-ed   Shield-ed   M18									~				-		-						
Shielded   Mila   Yes   No			3 11111	No												with Self-					
Manual Park																					
Peter to   No   No   No   No   No   No   No			1440	Yes		_					_				-						
No		Cu				_	_					-			-						
No			,	No												with con-					
No   No   No   No   No   No   No   No												-			connector						
No   No   No   No   No   No   No   No	DC	10 mm	Yes		_							_		_							
ACIDE Shield Fed M12 2 mm M30 13 mm M30 18 mm								~				-		-	page 9.						
ACIDIC   Shield Feel   Mag				No									_								
A mm   M12   M18   M18			MR										_			Refer to					
No									-			-		-	-	page 8.					
Un-shielded   M18   Ham   Yes   NO			M12					•		•	•	•	•		•						
AC/DC Shield-ed		l In-						_					_		•	with Self- diagnostic					
AC   Man		shield- ed M18 14 mm	shield- M18	shield- M18	shield- M18	Yes				•		•	•		•		•	Output or			
AC/DC Shield ed			14 mm			NC				•			•	•		•					
AC/DC Shield ed					NO			•	●▲□■	•	•	●▲□	•		•	ventional					
AC/DC Shield-ed M18					NC				•			•			•	pin assign- ments on					
AC/DC Shield- ed			M8		NO				•								29.				
AC/DC Shield-ed   Shield-ed   M18   5 mm   M30   M10   M10					NC				•												
AC/DC Shield-ed			M12		NO				•		•	•									
AC/DC Shield-ed      M12		Shield-	2 mm		NC				•			•									
AC/DC Shield-ed		ed	M18		NO				••		•	•									
AC/DC Shield-ed			5 mm		NC				•			•									
AC Un-shield-ed									●▲		•	•									
M8 2 mm	AC		10 mm	mm					•			•									
NO   NO   NO   NO   NO   NO   NO   NO									-												
Un-shield-ed			2 mm						~							Refer					
AC/DC Shielded M18 5 mm M30 NO		l In-																			
AC/DC Shielded M18 5 mm M30 NO NO NO																					
AC/DC Shielded M18 5 mm M30 NO		ed														-					
AC/DC Shielded M18 5 mm M30 MO																					
AC/DC Shielded M18 5 mm M30 M30 M0																-					
AC/DC Shielded M18 5 mm M30 MO																-					
AC/DC Shielded M18 5 mm M30 M0																-					
AC/DC ed 5 mm NC		Chi-1-														-					
M30 NO	AC/DC								-							1					
		ed					5 mm	-												-	
			10 mm		NC											1					

 $\bullet$ : Standard Models,  $\blacktriangle$ : Different frequency, ---: Not listed

# **3-Wire Models**

		listance			Oil-res reinfo PUR	orced		(cable m		d cable a			models		Pa	ige											
Power supply	Shielding	Size and sensing distance	Polarity	Operation mode	M12 pre-wired smartclick connector models	Pre-wired model with 2-m cable	M12 pre-wired smartclick connector models	Pre-wired model with standard 2-m cable	Pre-wired model with flexible 2-m cable	Pre-wired model with standard 5-m cable	M12 connector (IEC pin arrangement)	M12 standard pre- wired connector models	M8 connector	e-CON pre-wired connector models	Ordering Information	Dimensions reference chart											
		3 dia. 0.6 mm		NO NC				•																			
		4 dia.		NO				•	•	•																	
		0.8 mm		NC				•																			
		M5		NO				•	•	•																	
		1 mm		NC				•							Refer to page 11.												
		5.4 dia.		NO				•	•	•																	
	Shield- ed	1 mm		NC				•																			
	Cu	M8 1.5mm		NO NC				•			•		•														
		M12		NO				•	•	•	•			•													
DC	2 mm	.,	NC				•			•																	
NPN		M18 5 mm	Yes	NO				•	•	•	•			•													
	5 mm M30 10 mm		NC				•			•																	
				NO				•	•	•	•			•													
				NC				•			•					_											
		M8 2 mm		NO NC				•			•		•														
		M12		NO				•	•	•	•			•													
	Un-	5 mm		NC				•			•				Refer												
	shield- ed	M18		NO				•	•	•	•			•	topage 12.												
		10 mm							NC				•			•				1							
		M30													1						NO				•4	•	•
		18 mm		NC				•			•					Refer to page											
		3 dia. 0.6 mm		NO				•								to page 29.											
				NC NO				•	•																		
		4 dia. 0.8 mm		NC				•																			
		M5		NO				•	•																		
		1 mm		NC				•																			
		5.4 dia.		NO				•							Dofor												
	Shield-	1 mm		NC				•							Refer to page												
	ed	M8 1.5mm		NO				•	•	•	•		•		11.												
				NC NO				•	•	•	•																
DC		M12 2 mm		NC				•			•																
DC PNP		M18	Yes	NO				•	•	•	•																
		5 mm		NC				•			•																
		M30		NO				•	•		•																
		10 mm		NC				•			•																
		M8 2 mm		NO				•	•		•		•		-												
				NC NO				•	•		•		•														
	Un-	M12 5 mm		NC				•			•				Refer												
	shield- ed	M18		NO				•	•		•				topage												
	eu	10 mm		NC				•			•				12.												
		M30		NO				•	•		•																
			M30 18 mm		NC				•			•															

# **E2E Guide to Selection by Purpose**



Note: Refer to Models Not Listed in this Catalog for Long Body Models, Transmission Couplers, and Power Couplers.

# **E2E Model Number Legend**

E2E-	1 2	3 4	5 6	7	- 8 9	- 10	- 📵 -	12	13
------	-----	-----	-----	---	-------	------	-------	----	----

No.	Classification	Code	Meaning	Remarks
1	Appearance	С	Cylindrical (not threaded)	
•	Appearance	Х	Cylindrical (threaded)	
	O a market market and a	Number	Sensing distance (Unit: mm)	Example:
2	Sensing distance	R	Indication of decimal point	R6: 0.6 mm 1R5: 1.5 mm
<b>(3</b> )	Shielding	Blank	Shielded Models	_
	g	М	Unshielded Models	
		В	DC 3-wire PNP open-collector output	_
		С	DC 3-wire NPN open-collector output	
	Power supply and output	D	DC 2-wire polarity/no polarity	Whether D models have
4	specifications	E	DC 3-wire NPN collector load built-in output	polarity is defined by num-
		F	DC 3-wire PNP collector load built-in output	ber ⑩.
		Т	AC/DC 2-wire	
		Υ	AC 2-wire	
<b>(5</b> )	Form of output switching el-	1	Normally open (NO)	
	ement	2	Normally closed (NC)	
<b>6</b>	Oscillation frequency type	Blank	Standard frequency	Used to prevent mutual in-
	Community type	5	Different frequency	terference.
7	Self-diagnosis	Blank	No	
•	Jon alagnosis	5	Yes	
		Blank	Pre-wired	These models are also available with e-CON
8	Connection method	M1	M12-size metal connector	connectors (0.3-m cable). Add "-ECON" to the end of
		МЗ	M8-size metal connector	the model number.
		Blank	Connector Models DC 3-wire and AC 2-wire, DC 2-wire with self-diagnosis output, DC 2-wire with old pin arrangement (polarity)	
		G	Connector Models DC 2-wire with IEC pin arrangement (polarity)	
9	Connector specifications	J	Pre-wired Connector Models DC 3-wire and AC 2-wire, DC 2-wire with IEC pin arrangement (polarity), DC 3-wire and AC 2-wire, DC 2-wire with self-diagnosis output, DC 2-wire with old pin arrangement (polarity)	
		GJ	Pre-wired Connector Models DC 2-wire with IEC pin arrangement (polarity)	
		TJ	Pre-wired Smartclick Connector Models DC 2-wire with IEC pin arrangement (no polarity)	
		TGJ	Pre-wired Smartclick Connector Models DC 2-wire with IEC pin arrangement (polarity)	
	DO Continue de altre	Blank	Polarity	
10	DC 2-wire polarity	Т	No polarity	-
		Blank	Standard PVC cable (oil resistant)	
11)	Cable specifications	R	Flexible PVC cable (oil resistant)	
		U	Polyurethane cable (oil resistant and reinforced)	
12	New model	N	New model (Applies only to DC 2-wire pre-wired and shielded models.)	This is blank if the cable specification in number (1) is R or U.
13	Cable length	Letter M	Cable length (Unit: m) (Applicable to Pre-wired Models and Pre-wired Connector Models.)	Example: 2M 0.3M
				I

Note: The purpose of this model number legend is to provide understanding of the meaning of specifications from the model number.

Models are not available for all combinations of code numbers.

Ask your OMRON representative if you require a customized model.

# **Ordering Information**

# 2-Wire Models

Shielded DC 2-wire Models with No Self-diagnostic Output [Refer to Dimensions on page 29.]



Appear- ance	Sensing distance	Connection method	Cable specifications	Polar- ity	Opera- tion mode	Pin arrangement	Applicable connector code *4	Model
		M12 Pre-wired Smart-	PUR (increased		NO	1: +V, 4: 0 V		E2E-X2D1-M1TGJ-U 0.3M
		click Connector Mod-	oil-resistant)		NC	1: +V, 2: 0 V	Н	E2E-X2D2-M1TGJ-U 0.3M
		els (0.3m)	PVC (oil-resistant)		NO	1: +V, 4: 0 V	G	E2E-X2D1-M1TGJ 0.3M
			PUR (increased		NO			E2E-X2D1-U 2M
		Pre-wired Models	oil-resistant)		NC			E2E-X2D2-U 2M
M8	2 mm	(2 m)	D) (O ( 'I	Yes	NO			E2E-X2D1-N 2M *2*3
			PVC (oil-resistant)		NC			E2E-X2D2-N 2M *3
		M12 Connector Mod-			NO	1: +V, 4: 0 V	Α	E2E-X2D1-M1G
		els			NC	1: +V, 2: 0 V	D	E2E-X2D2-M1G
					NO	1: +V, 4: 0 V		E2E-X2D1-M3G
		M8 Connector Models			NC	1: +V, 2: 0 V	ı	E2E-X2D2-M3G
		M10 Dro wired Cmort	PUR (increased		NO	1: +V, 4: 0 V		E2E-X3D1-M1TGJ-U 0.3M
		M12 Pre-wired Smart- click Connector Mod-	oil-resistant)		NC	1: +V, 2: 0 V	Н	E2E-X2D2-M1TGJ-U 0.3M E2E-X2D1-M1TGJ 0.3M E2E-X2D1-U 2M E2E-X2D2-U 2M E2E-X2D1-N 2M *2*3 E2E-X2D2-N 2M *3 E2E-X2D1-M1G E2E-X2D2-M1G E2E-X2D1-M3G
		els (0.3m)	PVC (oil-resistant)		NO	1: +V, 4: 0 V	G	E2E-X3D1-M1TGJ 0.3M
			PUR (increased		NO	·		E2E-X3D1-U 2M
		Pre-wired Models	oil-resistant)	Yes	NC			E2E-X3D2-U 2M
		(2 m)			NO			E2E-X3D1-N 2M *1*2*3
M12	3 mm		PVC (oil-resistant)		NC			
		M12 Connector Mod-			NO	1: +V, 4: 0 V	A	E2E-X3D1-M1G *1
		els			NC	1: +V, 2: 0 V	D	E2E-X3D2-M1G
					NO	1: +V, 4: 0 V	A	
		M12 Standard Pre-		Yes	NC	1: +V, 2: 0 V	D	E2E-X3D2-M1GJ 0.3M
		wired Connector Mod- els (0.3 m) *6	PVC (oil-resistant)		NO	(3, 4): (+V, 0 V)	С	
		Cis (0.0 iii) 0		No *5	NC	(1, 2): (+V, 0 V)	D	
			PUR (increased		NO	1: +V, 4: 0 V		E2E-X7D1-M1TGJ-U 0.3M
		M12 Pre-wired Smart- click Connector Mod-	oil-resistant)		NC	1: +V, 2: 0 V	Н	
		els (0.3m)	PVC (oil-resistant)		NO	1: +V, 4: 0 V	G	
			PUR (increased		NO	,		
		Pre-wired Models	oil-resistant)	Yes	NC			
		(2 m)		. 00	NO			
M18	7 mm		PVC (oil-resistant)		NC	-		
14110	/ !!!!!	M10 Connector Med			NO	1: +V, 4: 0 V	Α	
		M12 Connector Mod- els			NC	1: +V, 2: 0 V	D	
					NO	1: +V, 4: 0 V	A	
		M12 Standard Pre-		Yes	NC	1: +V, 2: 0 V	D	
		wired Connector Mod-	PVC (oil-resistant)		NO	(3, 4): (+V, 0 V)	С	
		els (0.3 m) *6		No *5	NC	(1, 2): (+V, 0 V)	D	
			DUD (		NO	1: +V, 4: 0 V		
		M12 Pre-wired Smart- click Connector Mod-	PUR (increased oil-resistant)		NC	1: +V, 2: 0 V	Н	
		els (0.3m)	PVC (oil-resistant)		NO	1: +V, 4: 0 V	G	
			` '		NO	1. +V, 4. 0 V	G	
			PUR (increased oil-resistant)	Yes	NC			
		Pre-wired Models (2 m)		169	NO			
M30	40	',	PVC (oil-resistant)		NC	-		
IVIOU	10 mm					1: .\/ 4: 0 \/	۸	
		M12 Connector Mod- els			NO	1: +V, 4: 0 V	A	
		3.0			NC	1: +V, 2: 0 V	D	
		M12 Standard Pre-		Yes	NO	1: +V, 4: 0 V	A	
		wired Connector Mod-	PVC (oil-resistant)		NC	1: +V, 2: 0 V	D	
		els (0.3 m) *6	` /	No *5	NO	(3, 4): (+V, 0 V)	С	
			el number is E2E-X □D15 (even		NC	(1, 2): (+V, 0 V)	D	E2E-X10D2-M1J-T 0.3M

<sup>\*1.</sup> Models with different frequencies are also available. The model number is E2E-X D15 (example: E2E-X3D15-N 2M).

\*2. Models with a flexible cable are also available. Add "-R" rather than "-N" to the end of the model number (example: E2E-X2D1-R 2M).

\*3. The standard stock includes models with a cable length of 5 m. Specify the cable length at the end of the model number. (Example: E2E-X3D1-N 5M)

\*4. Refer to page 24 for details.

\*5. The residual voltage for models without polarity is 5 V, so use caution concerning the connection load interface conditions (e.g., PLC ON voltage). Refer to page 28.

\*6. The standard cable length is 300 mm. Cables with a length of 500 mm and 1 m can also be manufactured.

# Unshielded DC 2-Wire Models with No Self-diagnosis Output [Refer to Dimensions on page 29.]



Appear- ance	Sensing o	listance	Connection method	Cable specifications	Polar- ity	Opera- tion mode	Pin arrangement	Applicable connector code *4	Model
			Pre-wired Models (2 m)	PVC (oil-resistant)		NO			E2E-X4MD1 2M *2*3
			Fre-wired Models (2 III)	PVC (oii-resistant)		NC			E2E-X4MD2 2M
M8	4 mm		M12 Connector Models			NO	1: +V, 4: 0 V	Α	E2E-X4MD1 2M
IVIO	4 111111		W12 Connector Models			NC	1: +V, 2: 0 V	D	E2E-X4MD2-M1G
			M8 Connector Models			NO	1: +V, 4: 0 V	1	E2E-X4MD1-M3G
			Wo Connector Wodels			NC	1: +V, 2: 0 V		E2E-X4MD2-M3G
			12M Pre-wired Smart- click Connector Models (0.3m)	PVC (oil-resistant)		NO	1: +V, 4: 0 V	G	E2E-X8MD1-M1TGJ 0.3M
			Pre-wired Models (2 m)	PVC (oil-resistant)		NO			E2E-X8MD1 2M *1*2*3
M12	0		Fre-wired Models (2 III)	PVC (oii-resistant)		NC			E2E-X8MD2 2M
IVI I Z	8 mm		M12 Connector Models			NO	1: +V, 4: 0 V	Α	E2E-X8MD1-M1G *1
			W12 Connector Models			NC	1: +V, 2: 0 V	D	E2E-X8MD2-M1G
			M12 Standard Pre-	DVC (eil registent)		NO	1: +V, 4: 0 V	Α	E2E-X8MD1-M1GJ 0.3M
			wired Connector Mod- els (0.3 m)	PVC (oil-resistant)		NC	1: +V, 2: 0 V	D	
			12M Pre-wired Smart- click Connector Models (0.3m)	PVC (oil-resistant)	Yes	NO	1: +V, 4: 0 V	G	E2E-X14MD1-M1TGJ 0.3M
			Due voice d Mardala (O. ca)	D) (C) (-ili-tt)		NO			E2E-X14MD1 2M *1*2*3
M18	4.4		Pre-wired Models (2 m)	PVC (oil-resistant)		NC			E2E-X14MD2 2M
IVI I O	14	mm	M12 Connector Models			NO	1: +V, 4: 0 V	Α	E2E-X14MD1-M1G *1
			W12 Connector Models			NC	1: +V, 2: 0 V	D	E2E-X14MD2-M1G
			M12 Standard Pre-	DVC (eil registent)		NO	1: +V, 4: 0 V	Α	E2E-X14MD1-M1GJ 0.3M
			wired Connector Mod- els (0.3 m)	PVC (oil-resistant)		NC	1: +V, 2: 0 V	D	E2E-X14MD2-M1GJ 0.3M
			12M Pre-wired Smart- click Connector Models (0.3m)	PVC (oil-resistant)		NO	1: +V, 4: 0 V	G	E2E-X20MD1-M1TGJ 0.3M
			Dre wired Medale (0 :)	DVC (eil regist==+\		NO			E2E-X20MD1 2M *1*2*3
M30		20 mm	Pre-wired Models (2 m)	PVC (oil-resistant)		NC			E2E-X20MD2 2M
IVIOU		20 mm	M12 Connector Models			NO	1: +V, 4: 0 V	Α	E2E-X20MD1-M1G *1
			IVITZ Confrector Models			NC	1: +V, 2: 0 V	D	E2E-X20MD2-M1G
			M12 Standard Pre-	DVC (all masks) 11		NO	1: +V, 4: 0 V	Α	E2E-X20MD1-M1GJ 0.3M
			wired Connector Mod- els (0.3 m)	PVC (oil-resistant)		NC	1: +V, 2: 0 V	D	

# Shielded DC 2-Wire Models with Self-diagnosis Output [Refer to Dimensions on page 29.]



Appear- ance	Sensing distance	Connection method	Cable specifications	Polar- ity	Opera- tion mode	Pin arrangement	Applicable connector code *2	Model
		Pre-wired Models (2 m)	PVC (oil-resistant)					E2E-X3D1S 2M *1
M12	3 mm	M12 Connector Models				2: +V and diagnostic output 3: 0 V 4: +V and control output	D	E2E-X3D1S-M1
		Pre-wired Models (2 m)	PVC (oil-resistant)					E2E-X7D1S 2M *1
M18	7 mm	M12 Connector Models		Yes	NO	2: +V and diagnostic output 3: 0 V 4: +V and control output	D	E2E-X7D1S-M1
-		Pre-wired Models (2 m)	PVC (oil-resistant)					E2E-X10D1S 2M *1
M30	10 mm	M12 Connector Models				2: +V and diagnostic output 3: 0 V 4: +V and control output	D	E2E-X10D1S-M1

<sup>\*1.</sup> Models with different frequencies are also available. The model number is E2E-X □D15S (example: E2E-X3D15S 2M). \*2. Refer to page 24 for details.



<sup>\*1.</sup> Models with different frequencies are also available. The model number is E2E-X \( \subseteq 15 \) (example: E2E-X8MD15 2M).

\*2. Models with a flexible cable are also available. Add -R to the end of the model number. (example: E2E-X4MD1-R 2M).

\*3. The standard stock includes models with a cable length of 5 m. Specify the cable length at the end of the model number. (Example: E2E-X4MD1 5M)

\*4. Refer to page 24 for details.

# Unshielded DC 2-Wire Models with Self-diagnosis Output [Refer to Dimensions on page 29.]




Appear- ance	Sensing distance	Connection method	Cable specifications	Polar- ity	Opera- tion mode	Pin arrangement	Applicable connector code *2	Model
		Pre-wired Mod- els (2 m)	PVC (oil-resistant)					E2E-X8MD1S 2M *
M12	8 mm	M12 Connector Models				2: +V and diagnostic output 3: 0 V 4: +V and control output	D	E2E-X8MD1S-M1
		Pre-wired Mod- els (2 m)	PVC (oil-resistant)					E2E-X14MD1S 2M *
M18	14 mm	M12 Connector Models		Yes	NO	2: +V and diagnostic output 3: 0 V 4: +V and control output	D	E2E-X14MD1S-M1
		Pre-wired Mod- els (2 m)	PVC (oil-resistant)					E2E-X20MD1S 2M *
M30	20 mm	M12 Connector Models				2: +V and diagnostic output 3: 0 V 4: +V and control output	D	E2E-X20MD1S-M1

<sup>\*1.</sup> Models with different frequencies are also available. The model number is E2E-X \( \text{\text{MD15S}} \) (example: E2E-X8MD15S 2M).

# **Connector Pin Assignments of DC 2-Wire Models**

- The connector pin assignments of each New E2E DC 2-Wire Model conform to IEC 947-5-2 Table III. (Only DC 2-Wire Models have been changed in comparison to the previous models.)
- The following models with conventional connector pin assignments are available as well. (Only NO Models can be used.)
   The cable at the right should also be used if the XW3A-P□45-G11 Connector Junction Box is already being used.

Cable length	Model
500 mm	XS2W-D421-BY1



## Models with conventional connector pin assignments are available as well.

A mmaay			Model									
Appeara	ance	NO	Applicable connector code *	NC	Applicable connector code *							
	M8	E2E-X2D1-M1	С	E2E-X2D2-M1	D							
Shielded	M12	E2E-X3D1-M1	С	E2E-X3D2-M1	D							
	M18	E2E-X7D1-M1	С	E2E-X7D2-M1	D							
	M30	E2E-X10D1-M1	С	E2E-X10D2-M1	D							
	M8	E2E-X4MD1-M1	С	E2E-X4MD2-M1	D							
Unshielded	M12	E2E-X8MD1-M1	С	E2E-X8MD2-M1	D							
	M18	E2E-X14MD1-M1	С	E2E-X14MD2-M1	D							
	M30	E2E-X20MD1-M1	С	E2E-X20MD2-M1	D							

Note: Refer to page 24 for details.

<sup>\*2.</sup> Refer to page 24 for details.

# AC 2-Wire Models Shielded Models [Refer to Dimensions on page 29.]



Appear- ance	Sensing distance		tance	Connection method	Cable specifications	Operation mode	Pin arrangement	Applicable con- nector code *3	Model
M8	<b>.</b>			Pre-wired Models	PVC (oil-resistant)	NO			E2E-X1R5Y1 2M
IVIO	1.5 m	m		(2 m)	r vo (on-resistant)	NC			E2E-X1R5Y2 2M
				Pre-wired Models	PVC (oil-resistant)	NO			E2E-X2Y1 2M *1*2
M12	2 mm	<u></u>		(2 m)	PVC (oii-resistant)	NC			E2E-X2Y2 2M
IVIIZ		M12 Connecto			NO	(3, 4): (AC, AC)	E	E2E-X2Y1-M1	
				Models		NC	(1, 2): (AC, AC)	F	E2E-X2Y2-M1
				Pre-wired Models	PVC (oil-resistant)	NO			E2E-X5Y1 2M *1*2
M18				(2 m)	PVC (oil-resistant)	NC			E2E-X5Y2 2M
IVI I O	5 m	m		M12 Connector		NO	(3, 4): (AC, AC)	E	E2E-X5Y1-M1
				Models		NC	(1, 2): (AC, AC)	F	E2E-X5Y2-M1
				Pre-wired Models	PVC (oil-resistant)	NO			E2E-X10Y1 2M *1*2
M30	10		(2 m)	r vo (oii-lesisialii)	NC			E2E-X10Y2 2M	
		10 mm		M12 Connector		NO	(3, 4): (AC, AC)	Е	E2E-X10Y1-M1
				Models		NC	(1, 2): (AC, AC)	F	E2E-X10Y2-M1

<sup>\*1.</sup> Models with different frequencies are also available. The model number is E2E-X \(\superscript{Y}\) (example: E2E-X5Y15 2M).

#### **Unshielded Models**



Appear- ance	Sensing di		stance	Connection method	Cable specifications	Operation mode	Pin arrangement	Applicable con- nector code *3	Model	
M8	<b>-</b> 0			Pre-wired Models	PVC (oil-resistant)	NO			E2E-X2MY1 2M	
IVIO	2 mm	1		(2 m)	FVC (oii-resistant)	NC			E2E-X2MY2 2M	
				Pre-wired Models	PVC (oil-resistant)	NO			E2E-X5MY1 2M *1*2	
M12	V410			(2 m)	FVC (oii-resistant)	NC			E2E-X5MY2 2M	
IVIIZ	5 m	irm 		M12 Connector		NO	(3, 4): (AC, AC)	E	E2E-X5MY1 2M	
				Models		NC	(1, 2): (AC, AC)	F	E2E-X5MY2-M1	
				Pre-wired Models	PVC (oil-resistant)	NO			E2E-X10MY1 2M *1	
M18		40		(2 m)	FVC (oii-resistant)	NC			E2E-X10MY2 2M	
IVITO		10 mm			M12 Connector		NO	(3, 4): (AC, AC)	E	E2E-X10MY1-M1
				Models		NC	(1, 2): (AC, AC)	F	E2E-X10MY2-M1	
				Pre-wired Models	PVC (oil-resistant)	NO			E2E-X18MY1 2M *1	
M30	Maa		_	(2 m)	r vo (on-resistant)	NC			E2E-X18MY2 2M	
IVIOU			18 mm	M12 Connector		NO	(3, 4): (AC, AC)	E	E2E-X18MY1-M1	
				Models		NC	(1, 2): (AC, AC)	F	E2E-X18MY2-M1	

<sup>\*1.</sup> Models with different frequencies are also available. The model number is E2E-X MY (example: E2E-X5MY15 2M).

# AC 2-Wire Models Shielded Models [Refer to Dimensions on page 29.]



Appear- ance	Sensing distance		Connection method	Cable specifications	Operation mode	Pin arrangement	Applicable con- nector code *3	Model
M12	3 mm		Pre-wired Models (2 m)	PVC (oil-resis- tant)				E2E-X3T1 2M
M18	7 mm		Pre-wired Models (2 m)	PVC (oil-resis- tant)	NO			E2E-X7T1 2M *
M30	10 mm		Pre-wired Models (2 m)	PVC (oil-resis- tant)				E2E-X10T1 2M

<sup>\*2.</sup> The standard stock includes models with a cable length of 5 m. Specify the cable length at the end of the model number. (Example: E2E-X2Y1 5M) \*3. Refer to page 24 for details.

<sup>\*2.</sup> The standard stock includes models with a cable length of 5 m. Specify the cable length at the end of the model number. (Example: E2E-X5MY1 5M) \*3. Refer to page 24 for details.

Note: Not compliant with CE.

\* The standard stock includes models with a cable length of 5 m. Specify the cable length at the end of the model number. (Example: E2E-X7T1 5M)

# Shielded DC 3-Wire Models [Refer to Dimensions on page 29.]



			Orbita	0		Appli-	Mo	del
Appear- ance	Sensing distance	Connection method	Cable specifica-tions	Opera- tion mode	Pin arrangement	cable connec- tor code *5	NPN output	PNP output
3 dia.	0.0 0.000	Pre-wired Models	PVC (oil-re-	NO			E2E-CR6C1 2M	E2E-CR6B1 2M
J dia.	0.6 mm	(2 m)	sistant)	NC			E2E-CR6C2 2M	E2E-CR6B2 2M
4 dia.	0.8 mm	Pre-wired Models	PVC (oil-re-	NO			E2E-CR8C1 2M *1*2	E2E-CR8B1 2M *2
4 dia.	0.0 111111	(2 m)	sistant)	NC			E2E-CR8C2 2M	E2E-CR8B2 2M
M5	1 mm	Pre-wired Models	PVC (oil-re-	NO			E2E-X1C1 2M *1*2	E2E-X1B1 2M *2
		(2 m)	sistant)	NC			E2E-X1C2 2M	E2E-X1B2 2M
5.4 dia.	1 mm	Pre-wired Models	PVC (oil-re-	NO			E2E-C1C1 2M *1*2	E2E-C1B1 2M
		(2 m)	sistant)	NC			E2E-C1C2 2M	E2E-C1B2 2M
		Pre-wired Models	PVC (oil-re- sistant)	NO			E2E-X1R5E1 2M *1*2	E2E-X1R5F1 2M *1*2
		(2 m)	PVC (oil-re- sistant)	NC			E2E-X1R5E2 2M	E2E-X1R5F2 2M
MO	M8 1.5 mm	M12 Connector		NO	1: +V, 3: 0 V, 4: Control output	В	E2E-X1R5E1-M1	E2E-X1R5F1-M1
IVIO		Models		NC	1: +V, 3: 0 V, 2: Control output	D	E2E-X1R5E2-M1	E2E-X1R5F2-M1
		M8 Connector		NO	1: +V, 3: 0 V, 4: Control output		E2E-X1R5E1-M3	E2E-X1R5F1-M3
		Models		NC	1: +V, 3: 0 V, 2: Control output	] '	E2E-X1R5E2-M3	E2E-X1R5F2-M3
		Pre-wired Models		NO			E2E-X2E1 2M *1*2*3*4	E2E-X2F1 2M *1*2*3
		(2 m)	sistant) NC				E2E-X2E2 2M	E2E-X2F2 2M
M12	2 mm	M12 Connector	2 Connector		1: +V, 3: 0 V, 4: Control output	В	E2E-X2E1-M1	E2E-X2F1-M1
		Models		NC	1: +V, 3: 0 V, 2: Control output	D	E2E-X2E2-M1	E2E-X2F2-M1
		Pre-wired Models (2 m)	PVC (oil-re- sistant)	NO			E2E-X5E1 2M *1*2*3*4	E2E-X5F1 2M *1*2*3
		(2 111)	SiStarit)	NC			E2E-X5E2 2M	E2E-X5F2 2M
M18	5 mm	M12 Connector		NO	1: +V, 3: 0 V, 4: Control output	В	E2E-X5E1-M1	E2E-X5F1-M1
		Models		NC	1: +V, 3: 0 V, 2: Control output	D	E2E-X5E2-M1	E2E-X5F2-M1
		Pre-wired Models	PVC (oil-re-	NO			E2E-X10E1 2M *1*2*3*4	E2E-X10F1 2M *2
		(2 m)	sistant)	NC			E2E-X10E2 2M	E2E-X10F2 2M
M30	10 mm	M12 Connector		NO	1: +V, 3: 0 V, 4: Control output	В	E2E-X10E1-M1	E2E-X10F1-M1
+4 - 71 - 1		Models		NC	1: +V, 3: 0 V, 2: Control output	D	E2E-X10E2-M1	E2E-X10F2-M1

<sup>\*1.</sup> The standard stock includes models with a cable length of 5 m. Specify the cable length at the end of the model number. (Example: E2E-X2E1 5M)
\*2. Models with a flexible cable are also available. Add -R to the end of the model number. (example: E2E-X5E1-R 2M).
\*3. Models with different frequencies are also available. The model number is E2E-X□□□5 (example: E2E-X5E15 2M).
\*4. Models with pre-wired e-CON connectors are also available (cable length: 0.3 m). Add "-ECON 0.3M" to the end of the model number. (Example: E2E-X2E1-ECON 0.3M)

\*5. Perfect to page 24 for details.

<sup>\*5.</sup> Refer to page 24 for details.

# Unshielded DC 3-Wire Models [Refer to Dimensions on page 29.]



								Appli-	Mo	del		
Appear- ance	Sensi	ing dis	tance	Connection method	Cable specifications	Opera- tion mode	Pin arrangement	cable connec- torcode *5	NPN output	PNP output		
				Pre-wired Models	PVC (oil-resis-	NO			E2E-X2ME1 2M *2	E2E-X2MF1 2M *2		
				(2 m)	tant)	NC			E2E-X2ME2 2M	E2E-X2MF2 2M		
				M12 Connector		NO	1: +V, 3: 0 V, 4: Control output	В	E2E-X2ME1-M1	E2E-X2MF1-M1		
M8	2 mm			Models		NC	1: +V, 3: 0 V, 2: Control output	D	E2E-X2ME2-M1	E2E-X2MF2-M1		
						M8 Connector		NO	1: +V, 3: 0 V, 4: Control output	1	E2E-X2ME1-M3	E2E-X2MF1-M3
				Models		NC	1: +V, 3: 0 V, 2: Control output	'	E2E-X2ME2-M3	E2E-X2MF2-M3		
				Pre-wired Models	PVC (oil-resis- tant)	NO			E2E-X5ME1 2M *1*2*3*4	E2E-X5MF1 2M *2		
				(2 m)	iani)	NC			E2E-X5ME2 2M	E2E-X5MF2 2M		
M12	5 mm	M12 Co	M12 Connector		NO	1: +V, 3: 0 V, 4: Control output	В	E2E-X5ME1-M1	E2E-X5MF1-M1			
				Models		NC	1: +V, 3: 0 V, 2: Control output	D	E2E-X5ME2-M1	E2E-X5MF2-M1		
				Pre-wired Models (2 m)	PVC (oil-resis- tant)	NO			E2E-X10ME1 2M *1*2*3*4	E2E-X10MF1 2M *2		
				(2 111)	iani)	NC			E2E-X10ME2 2M	E2E-X10MF2 2M		
M18	1	0 mm		M12 Connector		NO	1: +V, 3: 0 V, 4: Control output	В	E2E-X10ME1-M1	E2E-X10MF1-M1		
				Models		NC	1: +V, 3: 0 V, 2: Control output	D	E2E-X10ME2-M1	E2E-X10MF2-M1		
				Pre-wired Models	PVC (oil-resis- tant)	NO			E2E-X18ME1 2M *1*2*3*4	E2E-X18MF1 2M *2		
	18 r		(2 m)	iaiii)	NC			E2E-X18ME2 2M	E2E-X18MF2 2M			
M30		18 mm M12 Connector		NO	1: +V, 3: 0 V, 4: Control output	В	E2E-X18ME1-M1	E2E-X18MF1-M1				
_				Models		NC	1: +V, 3: 0 V, 2: Control output	D	E2E-X18ME2-M1	E2E-X18MF2-M1		

<sup>\*1.</sup> The standard stock includes models with a cable length of 5 m. Specify the cable length at the end of the model number. (Example: E2E-X5ME1 5M)

\*2. Models with a flexible cable are also available. Add -R to the end of the model number. (example: E2E-X5E1-R 2M).

\*3. Models with different frequencies are also available. The model number is E2E-X□M□□5 (example: E2E-X5ME15 2M).

\*4. Models with pre-wired e-CON connectors are also available (cable length: 0.3 m). Add "-ECON 0.3M" to the end of the model number. (Example: E2E-X2E1-ECON 0.3 m).

<sup>0.3</sup>M)
\*5. Refer to page 24 for details.

# **Ratings and Specifications**

#### E2E-X D DC 2-Wire Models

Size		N	18	М	12	M	18	N	/I30		
	Shielded	Shielded	Unshielded	Shielded	Unshielded	Shielded	Unshielded	Shielded	Unshielded		
ltem	Model	E2E-X2D□	E2E-X4MD□	E2E-X3D□	E2E-X8MD□	E2E-X7D□	E2E-X14MD	E2E-X10D□	E2E-X20MD		
Sensing	distance	2 mm ±10%	4 mm ±10%	3 mm ±10%	8 mm ±10%	7 mm ±10%	14 mm ±10%	10 mm ±10%	20 mm ±10%		
Set dista	ance *1	0 to 1.6 mm	0 to 3.2 mm	0 to 2.4 mm	0 to 6.4 mm	0 to 5.6 mm	0 to 11.2 mm	0 to 8 mm	0 to 16 mm		
Differen	tial travel	15% max. of ser	15% max. of sensing distance 10% max. of sensing distance								
Detectal	ble object	Ferrous metal (7	Ferrous metal (The sensing distance decreases with non-ferrous metal. Refer to Engineering Data on pages 18 and 19.								
Standar object	d sensing	Iron, 8 × 8 × 1 mm	Iron, $20 \times 20 \times 1 \text{ mm}$	Iron, 12 × 12 × 1 mm	Iron, $30 \times 30 \times 1 \text{ mm}$	Iron, 18 × 18 × 1 mm	Iron, 30 × 30 × 1	$\begin{array}{c c} \text{Iron,} \\ 54 \times 54 \times 1 \text{ n} \end{array}$			
Respons	se frequency	1.5 kHz	1 kHz	0.8 kHz				0.1 kHz			
Power supply voltage (operating voltage range)		12 to 24 VDC (10 to 30 VDC), ripple (p-p): 10% max.									
Leakage current		0.8 mA max.									
Load current 3 to 100 mA, Diagnostic output: 50 mA for -D1(5)S Models											
Control output	Residual voltage *3	3 V max. (Load	current: 100 mA,	Cable length: 2 m	, M1J-T Models o	nly: 5 V max.)					
Indicato	rs	D1 Models: Ope D2 Models: Ope	ration indicator (r ration indicator (r	ed) and setting inded)	dicator (green)						
Operation mode (with sensing object approaching)  D1 Models: NO D2 Models: NC  Refer to the timing charts under I/O Circuit Diagrams on page 21 for details.											
Diagnostic output delay 0.3 to 1 s											
Protection circuits Surge suppressor, Load short-circuit protection (for control and diagnostic output)											
Ambient temperature range Operating: -25 to 70°C, Storage: -40 to 85°C (with no icing or condensation)											
Ambient humidity		Operating/storage: 35% to 95% (with no condensation)									
Tempera influenc		±15% max. of sensing distance at 23°C in the temperature range of –25 to 70°C ±10% max. of sensing distance at 23°C in the temperature range of –25 to 70°C									
Voltage	influence	$\pm 1\%$ max. of sensing distance at rated voltage in the rated voltage $\pm 15\%$ range									
Insulatio	on resistance	50 M $\Omega$ min. (at 500 VDC) between current-carrying parts and case									
Dielectri	ic strength	1000 VAC, 50/60 Hz for 1 minute between current carry parts and case									
Vibratio	n resistance	Destruction: 10	to 55 Hz, 1.5-mm	double amplitude	for 2 hours each	in X, Y, and Z dir	ections				
Shock re	esistance	Destruction: 500 10 times each in Z directions		Destruction: 1,0	00 m/s <sup>2</sup> 10 times	each in X, Y, and	Z directions				
Degree (	of protection		ls: IEC 60529 IP6 els: IEC 60529 IP6	7, in-house stand 67	ards: oil-resistant						
Connect	tion method	Pre-wired Mode	ls (Standard cable	e length: 2 m), Co	nnector Models, o	or Pre-wired Conn	ector Models (Sta	andard cable len	gth: 0.3 m)		
	Pre-wired Models	Approx. 60 g		Approx. 70 g		Approx. 130 g		Approx. 175 g			
Weight (pack- ed state)	Pre-wired Connector Models	-		Approx. 40 g		Approx. 70 g		Approx. 110 g			
	Connector Models	Approx. 15 g		Approx. 25 g		Approx. 40 g		Approx. 90 g			
	Case	Stainless steel (	SUS303)	Nickel-plated bra	ass						
Materi-	Sensing sur- face	PBT									
als	Clamping nuts	Nickel-plated bra	ass								
	Toothed washer Zinc-plated iron										

<sup>\*1.</sup> Use the E2E within the range in which the setting indicator (green LED) is ON (except D2 Models).

\*2. The response frequency is an average value.

Measurement conditions are as follows: standard sensing object, a distance of twice the standard sensing object, and a set distance of half the sensing distance.

\*3. The residual voltage of each M1J-T Model is 5 V. When connecting to a device, make sure that the device can withstand the residual voltage. (Refer to page 28 for

# **E2E-X**□**Y**□ **AC 2-Wire Models**

Size		N	Л8	N	M12		118	M30		
	Shielded	Shielded	Unshielded	Shielded	Unshielded	Shielded	Unshielded	Shielded	Unshielded	
Item	Model	E2E-X1R5Y	E2E-X2MY□	E2E-X2Y□	E2E-X5MY□	E2E-X5Y□	E2E-X10MY	E2E-X10Y	E2E-X18MY	
Sensing d	listance	1.5 mm ±10%	2 mm ±10%	1	5 mm ±10%	1	10 mm ±10%	1	18 mm ±10%	
Set distan	ce	0 to 1.2 mm	0 to 1.6 mm		0 to 4 mm		0 to 8 mm		0 to 14 mm	
Differentia	al travel	10% max. of se	nsing distance							
Detectable	e object	Ferrous metal (*	The sensing dista	nce decreases w	ith non-ferrous me	tal. Refer to <i>Engi</i>	ineering Data on p	page 19.)		
Standard s	sensing	Iron, 8 × 8 × 1 mm	Iron, 12 × 12 ×	1 mm	Iron, 15 × 15 × 1 mm	Iron, 18 × 18 × 1 mm	Iron, 30 × 30 ×	1 mm	Iron, 54 × 54 × 1 mm	
Response	frequency	25 Hz	1		- I	1	Ш.			
Power sup (operating range)*1	oply voltage g voltage	24 to 240 VAC (	(20 to 264 VAC),	50/60 Hz						
Leakage c	urrent	1.7 mA max.								
Control Load current 2 5 to 100 mA				5 to 200 mA		5 to 300 mA				
output	Residual voltage	Refer to Engine	ering Data on pag	ge 20.						
Indicators	1	Operation indica	ator (red)							
Operation (with sens approachi	sing object	Y1 Models: NO Y2 Models: NC	Refer to the ti	ming charts unde	er I/O Circuit Diagra	ams on page 23 fo	or details.			
Protection circuits Surge suppressor										
Ambient to range *1*2	t temperature Operating/Storage: -25 to 70°C (with no icing or condensation)  Operating/Storage: -40 to 85°C (with no icing or condensation)									
Ambient humidity r										
Temperatu influence	ure	±10% max. of seat 23°C in the te of -25 to 70°C	ensing distance mperature range		sensing distance a sensing distance a					
Voltage in	fluence	±1% max. of se	nsing distance at	rated voltage in t	he rated voltage ±	15% range				
Insulation	resistance	50 MΩ min. (at	500 VDC) betwee	en current-carryin	g parts and case					
Dielectric	strength	4,000 VAC (M8	Models: 2,000 V	AC), 50/60 Hz for	1 min between cu	rrent-carrying par	ts and case			
Vibration	resistance	Destruction: 10 to 55 Hz, 1.5-mm double amplitude for 2 hours each in X, Y, and Z directions								
Shock res	istance	Destruction: 500 10 times each in Z directions		Destruction: 1,0	000 m/s <sup>2</sup> 10 times	each in X, Y, and	Z directions			
Degree of	protection		ls: IEC 60529 IP6 els: IEC 60529 IP		dards: oil-resistant					
Connectio	n method	Pre-wired Mode	ls (Standard cabl	e length: 2 m) an	d Connector Mode	els				
Weight	Pre- wired Models Model	Approx. 60 g		Approx. 70 g		Approx. 130 g		Approx. 175 g		
J	Connector Models	Approx. 15 g		Approx. 25 g		Approx. 40 g		Approx. 90 g		
	Case	Stainless steel (	SUS303)	Nickel-plated b	rass	•				
	Sensing surface	PBT								
Materials	Clamp- ing nuts	Nickel-plated br	ass							
	Toothed washer	Zinc-plated iron								
Accessori	ies	Instruction man	ual							
	· ·		·							

<sup>\*1.</sup> When supplying 24 VAC to any of the above models, make sure that the operating ambient temperature range is at least -25°C.
\*2. When using an M18 or M30 Connector Model at an ambient temperature between 70 and 85°C, make sure that the Sensor has a control output (load current) of 5 to 200 mA max.

# E2E-X□T1 AC/DC 2-Wire Models

	Size	M12	M18	M30				
	Shielded		Shielded					
Item	Model	E2E-X3T1	E2E-X7T1	E2E-X10T1				
Sensing dista	nce	3 mm ±10%	7 mm ±10%	10 mm ±10%				
Set distance		0 to 2.4 mm	0 to 5.6 mm	0 to 8 mm				
Differential tra	avel	10% max. of sensing distance						
Detectable ob	ject	Ferrous metal (The sensing distance	decreases with non-ferrous metal. R	efer to <i>Engineering Data</i> on page 18.				
Standard sens	sing object	Iron, 12 × 12 × 1 mm	Iron, 18 × 18 × 1 mm	Iron, 30 × 30 × 1 mm				
Response	DC	1 kHz	0.5 kHz	0.4 kHz				
frequency *1	AC	25 Hz	1					
Power supply (operating vol	voltage Itage range) *2	24 to 240 VDC (20 to 264 VDC) 48 to 240 VAC (40 to 264 VAC)						
Leakage curre	ent	DC: 1 mA max. AC: 2 mA max.						
Control	Load current	5 to 100 mA						
output	Residual voltage	DC: 6 V max. (Load current: 100 mA, Cable length: 2 m) AC: 10 V max. (Load current: 5 mA, Cable length: 2 m)						
Indicators		Operation indicator (red), Setting ind	licator (green)					
Operation mode (with sensing object approaching)		NO (Refer to the timing charts under	I/O Circuit Diagrams on page 21 for	details.)				
Protection circuits		Load short-circuit protection (20 to 4	0 VDC only), Surge suppressor					
Ambient temp	erature range	Operating: -25 to 70°C, Storage: -40 to 85°C (with no icing or condensation)						
Ambient hum	idity range	Operating/Storage: 35% to 95% (with no condensation)						
Temperature i	influence	±10% max. of sensing distance at 23°C in the temperature range of –25 to 70°C						
Voltage influe	ence	$\pm 1\%$ max. of sensing distance at rated voltage in the rated voltage $\pm 15\%$ range						
Insulation res	istance	50 MΩ min. (at 500 VDC) between current-carrying parts and case						
Dielectric stre	ength	4,000 VAC, 50/60 Hz for 1 minute be	etween current-carrying parts and cas	e				
Vibration resi	stance	Destruction: 10 to 55 Hz, 1.5-mm do	uble amplitude for 2 hours each in X,	Y, and Z directions				
Shock resista	nce	Destruction: 1,000 m/s <sup>2</sup> 10 times each	ch in X, Y, and Z directions					
Degree of pro	tection	IEC 60529 IP67, in-house standards	: oil-resistant					
Connection m	nethod	Pre-wired Models (Standard cable le	ength: 2 m)					
Weight (packe	ed state)	Approx. 80 g	Approx. 140 g	Approx. 190 g				
	Case	Nickel-plated brass						
	Sensing surface	РВТ						
Materials	Clamping nuts	Nickel-plated brass						
	Toothed washer	Zinc-plated iron						
Accessories		Instruction manual						

<sup>\*1.</sup> The response frequency is an average value. Measurement conditions are as follows: standard sensing object, a distance of twice the standard sensing object, and a set distance of half the sensing distance.
\*2. Power Supply Voltage Waveform:
Use a sine wave for the power supply. Using a rectangular AC power supply may result in faulty reset.

# E2E-X□E□/F□ DC 3-Wire Models

	Size	N	18	N	<i>I</i> 112	M	18	M30		
	Shielded	Shielded	Unshielded	Shielded	Unshielded	Shielded	Unshielded	Shielded	Unshielded	
Item	Model	E2E -X1R5E□/F□	E2E -X2ME□/F□	E2E -X2E□/F□	E2E -X5ME□/F□	E2E -X5E□/F□	E2E -X10ME□/F□	E2E-X10E□/ F□	E2E -X18ME□/F□	
Sensing di	istance	1.5 mm ±10%	2 mm ±10%		5 mm ±10%		10 mm ±10%	18 mm ±10%		
Set distan	се	0 to 1.2 mm	0 to 1.2 mm 0 to 1.6 mm 0 to 4 mm 0 to 8 mm 0 to 14 mm							
Differentia	ıl travel	10% max. of sensing distance								
Detectable	object	Ferrous metal (The sensing distance decreases with non-ferrous metal. Refer to Engineering Data on pages 18 and 19.)								
Standard s	sensing	Iron, 8 × 8 × 1 mm	Iron, 12 × 12 × 1 mm		Iron, 15 ×15 × 1 mm	Iron, 18 × 18 × 1 mm	Iron, 30 × 30 × 1 mm		Iron, 54 × 54 × 1 mm	
Response frequency *1		2 kHz	0.8 kHz	1.5 kHz	0.4 kHz	0.6 kHz	0.2 kHz	0.4 kHz	0.1 kHz	
Power sup (operating range) *2	oply voltage voltage	12 to 24 VDC (10 to 40 VDC), ripple (p-p): 10% max.								
Current co	onsumption	13 mA max.								
	Load current *2	200 mA max.	200 mA max.							
	Residual voltage	2 V max. (Load	/ max. (Load current: 200 mA, Cable length: 2 m)							
Indicators		Operation indica	ator (red)							
	ation mode sensing object paching)  E1/F1 Models: NO E2/F2 Models: NC Refer to the timing charts under I/O Circuit Diagrams on page 21 for details.									
Protection	rotection circuits Load short-circuit protection, Surge suppressor, Reverse polarity protection									
Ambient temperatu	re range *2	Operating/Storage: –40 to 85°C (with no icing or condensation)								
Ambient h range	umidity	Operating/Stora	ge: 35% to 95% (	(with no condensa	ation)					
Temperatu influence	ıre	±15% max. of se ±10% max. of se	ensing distance a ensing distance a	t 23°C in the tem t 23°C in the tem	perature range of perature range of	–40 to 85°C –25 to 70°C				
Voltage in	fluence	±1% max. of ser	nsing distance at	rated voltage in t	he rated voltage ±	15% range				
Insulation	resistance	50 M $\Omega$ min. (at 500 VDC) between current-carrying parts and case								
Dielectric	strength	1,000 VAC, 50/60 Hz for 1 minute between current carry parts and case								
Vibration r	resistance	Destruction: 10 to 55 Hz, 1.5-mm double amplitude for 2 hours each in X, Y, and Z directions								
Shock resi	istance	Destruction: 500 10 times each in Z directions		Destruction: 1,0	000 m/s <sup>2</sup> 10 times	each in X, Y, and	Z directions			
Degree of	protection		ls : IEC 60529 IF els : IEC 60529 IF		ndards: oil-resistar	nt				
Connectio	n method	Pre-wired Mode	ls (Standard cabl	e length: 2 m) an	d Connector Mode	ls				
	Pre- wired Models	Approx. 65 g		Approx. 75 g		Approx. 150 g		Approx. 195 g		
Weight	Connector Models	Approx. 15 g		Approx. 25 g		Approx. 40 g		Approx. 90 g		
	Case	Stainless steel (	SUS303)	Nickel-plated b	rass	1		1		
	Sensing surface	РВТ		ı						
Materials	Clamp- ing nuts	Nickel-plated br	ass							
	Toothed washer	Zinc-plated iron								
Accessori	es	Instruction manu	ual							
		i								

<sup>\*1.</sup> The response frequency is an average value. Measurement conditions are as follows: standard sensing object, a distance of twice the standard sensing object, and a set distance of half the sensing distance.
\*2. When using an M8 Model at an ambient temperature between 70 and 85°C, supply 10 to 30 VDC to the Sensor and make sure that the Sensor has a control output of 100 mA maximum.

# E2E-C□C/B□ and E2E-X1C/B□ DC 3-Wire Models

	Size	3 dia.	4 dia.	M5	5.4 dia.				
	Shielded		S	hielded					
Item	Model	E2E-CR6C/B□	E2E-CR8C/B□	E2E-X1C/B□	E2E-C1C/B□				
Sensing d	listance	0.6 mm ±15%	0.8 mm ±15%	1 mm ±15%					
Set distan	ice	0 to 0.4 mm	0 to 0.5 mm	0 to 0.7 mm					
Differentia	al travel	15% max. of sensing distance							
Detectable	e object	Ferrous metal (The sensing dista	nce decreases with non-ferrous	metal. Refer to <i>Engineering Data</i> on p	ages 18 and 19.)				
Standard ject	sensing ob-	Iron, $3 \times 3 \times 1$ mm	Iron, $5 \times 5 \times 1$ mm						
Response	frequency *	2 kHz	3 kHz						
Power sup (operating range)	pply voltage g voltage	12 to 24 VDC (10 to 30 VDC), ripple (p-p): 10% max.							
Current co	onsumption	10 mA max.	17 mA max.						
Control output Residual voltage		Open-collector output, 80 mA max. (30 VDC max.)	Open-collector output, 100 mA	max. (30 VDC max.)					
		1 V max. (Load current: 80 mA, Cable length: 2 m) 2 V max. (Load current: 100 mA, Cable length: 2 m)							
Indicators		Operation indicator (red)							
Operation mode (with sensing object approaching)  C1/B1 Models: NO C2 Models: NC  Refer to the timing charts under I/O Circuit Diagrams on page 22 for details.									
Protection	n circuits	Reverse polarity protection, Surge							
Ambient temperatu	ıre range	Operating/Storage: -25 to 70°C (	with no icing or condensation)						
Ambient h	numidity	Operating/Storage: 35% to 95% (with no condensation)							
Temperati ence	ure influ-	$\pm 15\%$ max. of sensing distance at 23°C in the temperature range of –25 to $70^{\circ}\text{C}$							
Voltage in	fluence	±5% max. of sensing distance at rated voltage in the rated voltage in the rated voltage ±2.5% max. of sensing distance at rated voltage in the rated voltage ±15% range							
Insulation	resistance	50 M $\Omega$ min. (at 500 VDC) betwee	n current-carrying parts and cas	e					
Dielectric	strength	500 VAC, 50/60 Hz for 1 min betw	veen current-carrying parts and	case					
Vibration	resistance	Destruction: 10 to 55 Hz, 1.5-mm	double amplitude for 2 hours ea	ich in X, Y, and Z directions					
Shock res	sistance	Destruction: 500 m/s <sup>2</sup> 10 times ea	ach in X, Y, and Z directions						
Degree of	protection	IEC 60529 IP66	IEC 60529 IP67, in-house star	dards: oil-resistant					
Connection	on method	Pre-wired Models (Standard cable	e length: 2 m)						
Weight (pa	acked state)	Approx. 60 g							
	Case	Stainless steel (SUS303)		Nickel-plated brass					
	Sensing surface	Heat-resistant ABS							
Materials	Clamping nuts	Nickel-plated brass (E2E-X1C/B	only)						
	Toothed washer	Zinc-plated iron (E2E-X1C/B□ on	ly)						
Accessori	ies	Instruction manual							


<sup>\*</sup> The response frequency is an average value. Measurement conditions are as follows: standard sensing object, a distance of twice the standard sensing object, and a set distance of half the sensing distance.

# **Engineering Data (Typical)**


# **Sensing Area**

# **Shielded Models**


#### E2E-X D /-X T1



# $E2E-X\Box E\Box /-X\Box Y\Box /-X\Box F\Box$




# E2E-C C -X C E2E-C B1/-X B




# **Unshielded Models**

# E2E-X MD




#### E2E-X ME -X MY -X MF




# Influence of Sensing Object Size and Material


# E2E-X2D




# E2E-X3D\(\pi/\-X3T1\)




# E2E-X7D /-X7T1




# E2E-X10D /-X10T1




# E2E-X4MD




## E2E-X8MD







# E2E-X1□/-C1□




# **Leakage Current**












# **Residual Output Voltage**


# E2E-X□D□













E2E-X□Y□ at 100 VAC



# E2E-X□Y□ at 200 VAC



# I/O Circuit Diagrams

# **E2E-X**□**D**□ **DC 2-Wire Models**

Operation mode	Model	Timing Chart	Output circuit
Without self-	E2E-X□D1-N E2E-X□D1-M1G(J) E2E-X□D1-(M1TGJ)-U E2E-X□D1-M3G	Non-sensing unstable sensing area sensing area Sensing object (%) 100 80 0	Polarity: Yes  Proximity Brown +V  Sensor Main Albure 0 V  Note: The load can be connected to either the +V or 0 V side.
diagnostic output: NO	E2E-X□D1-M1J-T	Rated sensing distance ON OFF (green) ON Operation on indicator (red) ON OFF Control output	Polarity: None  Proximity (0 V)  Sensor main circuit (0 V)  Note 1. The load can be connected to either the +V or 0 V side.  2. The E2E-X□D1-M1J-T has no polarity. Therefore, terminals 3 and 4 have no polarity.
Without self- diagnostic output: NC	E2E-X□D2-N E2E-X□D2-M1G E2E-X□D2-(M1TGJ)-U E2E-X□D2-M3G	Non-sensing area  Sensing object  (%) 100 0  Rated sensing distance  ON Operation indicator (red) ON OFF  ON ON Control output	Proximity Bissensor main circuit  2 Bissensor Main circuit  2 Bissensor Main circuit  2 O V  Note: The load can be connected to either the +V  or 0 V side.
With self- diagnostic output: NO	E2E-X□D1S E2E-X□D1S-M1	Unstable Set position Sensing area  Stable sensing area  Stable sensing area  Proximity Sensor  Sensing object  (%) 100 80 0  Rated sensing distance  OFF Setting indicator (green)  OFF Control output  ON  OFF Diagnostic output*  * The diagnostic output is ON when there is a coil burnout or the sensing object is located in the unstable sensing area for 0.3 s or longer.	Prox Load +V Orange (2) (diagnostic output) Blue (3)  Note: Connect both the loads to the +V side of the control output and diagnostic output.


# **DC 3-Wire Models**

Operation mode	Output specifica- tions	Model	Timing Chart	Output circuit
NO	E2E-X□E□   NPN output   E2E-X□E□-M1   -		Sensing Present object Not present Operation ON indicator (red) OFF Control output (between brown and black leads) OFF Output voltage (between black and blue leads)	Proximity Sensor main circuit Black Tr
NC	The Couput	E2E-X□E□-M3	Sensing object Present Not present Operation indicator ON (red) OFF Control output (between brown and black leads) OFF Output voltage (between black and blue leads) Low	*Constant current output is 1.5 to 3 mA.  Note: For Connector Models, the connection between pins 1, 4 and 3 uses an NO contact, and the connection between pins 1, 2 and 3 uses an NC contact.
NO	- PNP output	E2E-X□F□ E2E-X□F□-M1	Sensing object  Present  Operation indicator (red)  Control output (Between blue and black leads)  Output voltage (between brown and black leads)  Low	Proximity Sensor Main circuit Black Load
NC	·	E2E-X□F□-M3	Sensing object Present Operation indicator (red) ON Control output (Between blue and black leads) OFF Output voltage (between brown and black leads) Low	*When a transistor is connected  Note: For Connector Models, the connection between pins 1, 4 and 3 uses an NO contact, and the connection between pins 1, 2 and 3 uses an NC contact.
NO	NPN open-		Sensing Present object Not present  Operation ON indicator (red) OFF  Control output  ON OFF	Proximity Sensor Black
NC	collector	E2E-C/X□C□	Sensing Present object Not present Operation ON indicator (red) OFF  Control ON output OFF	*The E2E-CR6□ does not have 100-Ω resistance.
NO	PNP open-	E2E-C/X□B□	Sensing Present object Not present Operation ON indicator (red) OFF  Control output OFF	Brown +V  Proximity Sensor main  Black
NC	- collector output		Sensing Present object Not present  Operation ON indicator (red) OFF  Control output OFF	*The E2E-CR6 $\square$ does not have 100- $\Omega$ resistance.

# **AC 2-Wire Models**

Operation mode	Model	Timing Chart	Output circuit
NO	E2E-X□Y□	Sensing Present object Not present  Operation ON indicator (red) OFF  Control output  Operate Reset	Proximity Sensor main circuit
NC	E2E-X□Y□-M1	Sensing Present object Not present Operation ON indicator (red) OFF Control Operate output Reset	Note: For Connector Models, the connection between pins 3 and 4 uses an NO contact, and the connection between pins 1 and 2 uses an NC contact.

# AC/DC 2-Wire Models



# e-CON Connectors

Requirement for e-CON Pre-wired Connector: A Connector is not provided with the Sensor. Be sure to order a Connector separately. [Dimensions: Inquire.]

Appearance	Cable length	Connector model number	Applicable Proximity Sensor model number	
Single-end connector	2 m	E39-ECON2M		
	5 m	E39-ECON5M		
Double-end connectors	0.5 to 1 m	E39-ECONW M	E2E-X□E□-ECON	
	1.1 to 1.5 m	$\square$ indicates cable length (in units of m).		
	1.6 to 2 m	Specify with 0.1-increments.		

OMRON

# **Sensor I/O Connectors**

Model for Connectors and Pre-wired Connectors: A Connector is not provided with the Sensor. Be sure to order a Connector separately. [Refer to Dimensions for the XS2, XS3, and XS5.]

_			Connector			
Applicable connector			Cable length 2m	Cable length 5m	Applicable Proximity Sensor model	Connection diagram
code	Screw	Appearance *1	CablConnector model number	CablConnector model number	number	No. *2
Α		Straight	XS2F-D421-DA0-A	XS2F-D421-GA0-A	F0F V□D1 M1C(I)	1
A		L-shape	XS2F-D422-DA0-A	XS2F-D422-GA0-A	E2E-X□D1-M1G(J)	1
В		Straight	XS2F-D421-DC0-A	XS2F-D421-GC0-A	E2E-X□E1-M1	10
Б		L-shape	XS2F-D422-DC0-A	XS2F-D422-GC0-A	E2E-X□F1-M1	10
		Straight	XS2F-D421-DD0	XS2F-D421-GD0	E2E-X□D1-M1J-T	3
С		Straight	X32F-D421-DD0	A32F-D42T-GD0	E2E-X□D1-M1	2
C		Labana	XS2F-D422-DD0	XS2F-D422-GD0	E2E-X□D1-M1J-T	3
		L-shape	X52F-D422-DD0	X52F-D422-GDU	E2E-X□D1-M1	2
					E2E-X□D2-M1G(J)	6
					E2E-X□D2-M1J-T	8
		Straight	XS2F-D421-D80-A	YS2F-D/21-G80-A	E2E-X□D2-M1	7
		Straight	X321 -D421-D00-A	XS2F-D421-G80-A	E2E-X□D1S-M1	5
D					E2E-X□E2-M1 E2E-X□F2-M1	11
U	M12				E2E-X□D2-M1G(J)	6
					E2E-X□D2-M1J-T	8
		L-shape	XS2F-D422-D80-A	XS2F-D422-G80-A	E2E-X□D2-M1	7
		L-Silape	X321 -D422-D00-A	A321 -D422-G00-A	E2E-X□D1S-M1	5
					E2E-X□E2-M1 E2E-X□F2-M1	11
Е		Straight	XS2F-A421-DB0-A	XS2F-A421-GB0-A	E2E-X□Y1-M1	14
_		L-shape	XS2F-A422-DB0-A	XS2F-A422-GB0-A		14
F		Straight	XS2F-A421-D90-A	XS2F-A421-G90-A	E2E-X□Y2-M1	15
G		Smartclick Connector, Straight	XS5F-D421-D80-A	XS5F-D421-G80-A	E2E-X□D1-M1TGJ	16
Н		Smartclick Connector, Straight	XS5F-D421-D80-P	XS5F-D421-G80-P	E2E-X□D1-M1TGJ-U	17
		Oil-resistant Reinforced Cables			E2E-X□D2-M1TGJ-U	18
					E2E-X□D1-M3G	4
					E2E-X□D2-M3G	9
		Straight	XS3F-M421-402-A	XS3F-M421-405-A	E2E-X□E1-M3 E2E-X□F1-M3	12
1	M8				E2E-X□E2-M3 E2E-X□F2-M3	13
•	IVIO				E2E-X□D1-M3G	4
					E2E-X□D2-M3G	9
		L-shape	XS3F-M422-402-A	XS3F-M422-405-A	E2E-X□E1-M3 E2E-X□F1-M3	12
					E2E-X□E2-M3 E2E-X□F2-M3	13

Note: Refer to Introduction to Sensor I/O Connectors for details and for information on Cable length and Robotics Cables. \*1. Images of straight and L-shaped connectors.









\*2. Refer to Connection Diagrams on page 25 for information on Proximity Sensor and I/O Connector connections.

# **Connections for Sensor I/O Connectors**

0	Connection Proximity Sensor		0			
diagram No.	Туре	Operation mode	Model	Sensor I/O Connector model number	Connections	
1	DC 2-wire (IEC pin wiring)		E2E-X□D1-M1G(J)	XS2F-D42A0-A D: 2-m cable G: 5-m cable	E2E XS2F	
2	DC 2-wire (previous pin wiring)		E2E-X□D1-M1	T: Straight 2: L-shape  XS2F-D42 - D0  D: 2-m cable G: 5-m cable	E2E XS2F  (a) (a) (b) (c) (c) (c) (c) (c) (c) (c) (c) (c) (c	
3	DC 2-wire (no polarity)	NO	E2E-X□D1-M1J-T	T: Straight 2: L-shape  XS2F-D42 - D0  D: 2-m cable G: 5-m cable	E2E XS2F    O	
4	DC 2-wire (M8 connector)		E2E-X□D1-M3G	T: Straight 2: L-shape  XS3F-M42□-40□-A 2: 2-m cable 5: 5-m cable	E2E XS3F *  O Brown (+) O White (not connected) O Blue (not connected) O Black (-)	
5	DC 2-wire (diagnostic type)		E2E-X□D1S-M1	T1: Straight 2: L-shape  XS2F-D42	E2E XS2F*  O Brown (not connected) O White (diagnostic output) (+) O Blue (0 V) O Black (control output) (+)	
6	DC 2-wire (IEC pin wiring)		E2E-X□D2-M1G(J)	1: Straight 2: L-shape  XS2F-D42	E2E XS2F*  O Brown (+) O White (-) O Blue (not connected) O Black (not connected)	
7	DC 2-wire (previous pin wiring)	NO	E2E-X□D2-M1	T1: Straight 2: L-shape XS2F-D42□-□80-A □ D: 2-m cable G: 5-m cable	E2E XS2F*  O Brown (not connected) O White (+) O Blue (-) O Black (not connected)	
8	DC 2-wire (no polarity)	NC	E2E-X□D2-M1J-T	T: Straight 2: L-shape  XS2F-D42 80-A  D: 2-m cable G: 5-m cable	E2E XS2F*  O Brown (+)(-) O White (-)(+) O Blue (not connected) Black (not connected)	
9	DC 2-wire (M8 connector)		E2E-X□D2-M3G	T1: Straight 2: L-shape  XS3F-M42□-40□-A 2: 2-m cable 5: 5-m cable	E2E XS3F *  O Brown (+) O White (-) O Blue (not connected) O Black (not connected)	

<sup>\*</sup> Different from Proximity Sensor wire colors.

Connection Proximity Sensor		Sensor I/O Connector			
diagram No.	Туре	Operation mode	Model	model number	Connections
10	DC 3-wire	NO	E2E-X□E/F1-M1	1: Straight 2: L-shape XS2F-D42□-□C0-A □ D: 2-m cable G: 5-m cable	E2E XS2F  O Brown (+V)  O Blue (0 V)  O Black (output)
11	- DC 3-wire	NC	E2E-X□E2/F2-M1	XS2F-D42	E2E XS3F  O Brown (+V)  O White (not connected)  O Blue (0 V)  O Black (output)
12	DC 3-wire	NO	E2E-X□E1/F1-M3	1: Straight 2: L-shape XS3F-M42□-40□-A 2: 2-m cable 5: 5-m cable	Brown (+V)  White (not connected)  Blue (0 V)  Black (output)
13	(M8 connector)	NC	E2E-X□E2/F2-M3	1: Straight 2: L-shape XS3F-M42□-40□-A 2: 2-m cable 5: 5-m cable	E2E XS3F  O Brown (+V) O White (output) O Blue (0 V) O Black (not connected)
14	- AC 2-wire	NO	E2E-X□Y1-M1	1: Straight 2: L-shape XS2F-A42 B0-A D: 2-m cable 6: 5-m cable	E2E XS2F  O Brown O Blue
15	AO 2-WIIE	NC	E2E-X□Y2-M1	XS2F-A421-□90-A D: 2-m cable G: 5-m cable	E2E XS2F*  O Brown O White O White (not connected)  Black (not connected)
16		NO	E2E-X□D1-M1TGJ	XS5F-D421-□80-A D: 2-m cable G: 5-m cable	E2E XSSF  O Brown (+) O White (not connected) O Blue (not connected) O Black (-)
17	DC 2-wire (Smartclick connector)	INO	E2E-X□D1- M1TGJ-U	XS5F-D421-□80-P D: 2-m cable G: 5-m cable	E2E XSSF  O Brown (+) O White (not connected) O Blue (not connected) O Black (-)
18		NC	E2E-X□D2- M1TGJ-U	XS5F-D421-□80-P  D; 2-m cable G: 5-m cable	E2E XS5F  Srown (+)  White (-)  Blue (not connected)  Black (not connected)

<sup>\*</sup> Different from Proximity Sensor wire colors.

Refer to Introduction to Sensor I/O Connectors for details.

# **Safety Precautions**

# Refer to Warranty and Limitations of Liability.

# ♠ WARNING

This product is not designed or rated for ensuring safety of persons either directly or indirectly. Do not use it for such purposes.



# CAUTION

- Do not short the load. Explosion or burning may
- Do not supply power to the Sensor with no load, otherwise Sensor may be damaged.

Applicable Models

E2E-CR6□

E2E-CR8 E2E-X1 E2E-C1



Item M8 M12 M18 M30


# **Precautions for Correct Use**

Do not use this product under ambient conditions that exceed the ratings.

#### Design

# **Influence of Surrounding Metal**

When mounting the Sensor within a metal panel, ensure that the clearances given in the following table are maintained. Failure to maintain these distances may cause deterioration in the performance of the Sensor.



# **Influence of Surrounding Metal**

Model

(Unit: mm)

Wiodei		Item	IVIO	IVI I Z	IVI I O	IVIOU	
		ı		C	)		
	Shielded	d	8	12	18	30	
		D	0				
DC 2-Wire Models		m	4.5	8	20	40	
E2E-X□D□		n	12	18	27	45	
AC/DC 2-Wire Models		I	12	15	22	30	
E2E-X□T1		d	24	40	70	90	
	Unshielded	D	12	15	22	30	
		e	8	20	40	70	
		n	24	40	70	90	
				C	)		
	Shielded	d	8	12	18	30	
202111 14 11		D	0				
DC 3-Wire Models E2E-X□E□		m	4.5	8	20	40	
E2E-X□F□		n	12	18	27	45	
AC 2-Wire Models			6	15	22	30	
E2E-X Y		d	24	40	55	90	
	Unshielded	D	6	15	22	30	
		m	8	20	40	70	
		n	24	36	54	90	
Model		Item	3 dia.	4 dia.	M5	5.4 dia.	
		1	o u.u.		-	011 0101	
DO 0 Mina Madala		d	3	4	5	5.4	
DC 3-Wire Models E2E-X□C/B□	Shielded	D		C			
E2E-C□C/B□		m	2	2.4	3	3	
		n	6	;	8	3	
			I				

### Relationship between Sizes and Models

	Model	Model
3 dia.		E2E-CR6C/B
4 dia.		E2E-CR8C□
4 ula.		E2E-CR8B□
ME	Shielded	E2E-X1C□
M5		E2E-X1B□
5.4		E2E-C1C□
dia.		E2E-C1B□
		E2E-X2D□
	Shielded	E2E-X1R5E□
	Sillelueu	E2E-X1R5F□
M8		E2E-X1R5Y□
IVIO		E2E-X4MD□
	Unshielded	E2E-X2ME□
	Orishleided	E2E-X2MF□
		E2E-X2MY□
		E2E-X3D□
		E2E-X2E□
	Shielded	E2E-X2F□
		E2E-X2Y□
M12		E2E-X3T1
		E2E-X8MD□
	Unshielded	E2E-X5ME□
	Unshleided	E2E-X5MF□
		E2E-X5MY□
		E2E-X7D□
		E2E-X5E□
	Shielded	E2E-X5F□
		E2E-X5Y□
M18		E2E-X7T1
		E2E-X14MD□
	Unshielded	E2E-X10ME□
	Orisinelaea	E2E-X10MF□
		E2E-X10MY□
		E2E-X10D□
		E2E-X10E□
	Shielded	E2E-X10F□
		E2E-X10Y□
M30		E2E-X10T1
		E2E-X20MD□
	Unshielded	E2E-X18ME□
	Orisinelaea	E2E-X18MF□
		E2E-X18MY□

**OMRON** 

#### **Mutual Interference**

When installing Sensors face-to-face or side-by-side, ensure that the minimum distances given in the following table are maintained.





#### **Mutual Interference**

(Unit: mm)

Model		Item	М8	M12	M18	M30
DC 2-Wire Models	Shielded	Α	20	30 (20)	50 (30)	100 (50)
E2E-X□D□	Silleided	В	15	20 (12)	35 (18)	70 (35)
AC/DC 2-Wire Models	Unshielded	Α	80	120 (60)	200 (100)	300 (100)
E2E-X□T1	Orisilielded	В	60	100 (50)	110 (60)	200 (100)
DC 3-Wire Models	Shielded	Α	20	30 (20)	50 (30)	100 (50)
E2E-X□E□/X□F□	Shleided	В	15	20 (12)	35 (18)	70 (35)
AC 2-Wire Models	Unshielded	Α	80	120 (60)	200 (100)	300 (100)
E2E-X□Y□	Orisinelded	В	60	100 (50)	110 (60)	200 (100)

Model		Item	3 dia.	4 dia.	M5	5.4 dia.
DC 3-Wire Models E2E-X□C/B□	Shielded	A 20			20	
E2E-C□C/B□	Officiaea	В			15	

Note: Values in parentheses apply to Sensors operating at different frequencies.

# Loads with Large Surge Currents (E2E-X□T□)

If a load with a large surge current is connected, such as a relay, lamp, or motor, the surge current may cause the load short-circuit protection circuit to operate, resulting in operating errors.


## Mounting

#### **Tightening Force**

Do not tighten the nut with excessive force. A washer must be used with the nut.








Note: 1. The allowable tightening strength depends on the distance from the edge of the head, as shown in the following table. (A is the distance from the edge of the head. B includes the nut on the head side. If the edge of the nut is in part A, the tightening torque for part A applies

2. The following strengths assume washers are being used.

Model		Par	Part A			
		Dimension	Torque			
M5	M5 1 N⋅m					
M8	Shielded	9	9 N⋅m	12 N·m		
IVIO	Unshielded	3	9 111111	12 11.111		
M12			30 N⋅m			
M18		70 N⋅m				
M30		180 N·m				

Refer to the following to mount the E2E-CR6, E2E-CR8 and E2E-C1 Unthreaded Cylindrical Models.



When using a set screw, tighten it to a torque of 0.2 N·m max. (E2E-C1: 0.4 N·m max.)

#### Connecting a DC 2-Wire Proximity Sensor to a PLC (Programmable Controller)

#### **Required Conditions**

Connection to a PLC is possible if the specifications of the PLC and the Proximity Sensor satisfy the following conditions. (The meanings of the symbols are given at the right.)

- The ON voltage of the PLC and the residual voltage of the Proximity Sensor must satisfy the following. Von ≤ Vcc- VR
- The OFF current of the PLC and the leakage current of the Proximity Sensor must satisfy the following. Ioff ≥ Ileal
  - (If the OFF current is not listed in the PLC's input specifications, take it to be 1.3 mA.)
- The ON current of the PLC and the control output of the Proximity Sensor must satisfy the following. lout (min.)  $\leq$  lout (max.)

The ON current of the PLC will vary, however, with the power supply voltage and the input impedance, as shown in the following equation. Ion = (Vcc - Vr - Vpc)/Rin

# Example

In this example, the above conditions are checked when the PLC Unit is the C200H-ID212, the Proximity Sensor is the E2E-X7D1-N, and the power supply voltage is 24 V.

- 1. Von  $(14.4 \text{ V}) \le \text{Vcc} (20.4 \text{ V}) \text{Vr} (3 \text{ V}) = 17.4 \text{ V}:\text{OK}$ OK
- 2. Ioff (1.3 mA) ≥ Ileak (0.8 mA):
- 3. Ion = [Vcc (20.4 V) VR (3 V) VPLc (4 V)]/Rin (3 k $\Omega$ ) = Approx. 4.5 mA Therefore, lout (min.) (3 mA)  $\leq$  lon (4.5 mA): OK Connection is thus possible.

- Von: ON voltage of PLC (14.4 V) Ion: ON current of PLC (typically 7 mA) IOFF: OFF current of PLC (1.3 mA) R<sub>IN</sub>: Input impedance of PLC (3  $k\Omega$ ) VPC: Internal residual voltage of PLC (4 V) VR: Output residual voltage of Proximity Sensor (3 V) Ileak: Leakage current of Proximity Sensor (0.8 mA)IOUT Control output of Proximity Sensor (3 to 100 mA) Vcc: Power supply voltage (PLC: 20.4 to 26.4 V) Values in parentheses apply to the following PLC
- model and Proximity Sensor model. C200H-ID212 PLC: Sensor: E2E-X7D1-N

# **Main Units**

# **Model Number-Dimensions Drawing Number Lookup Table**

Model		DC 2-Wire Models		DC 3-Wire Models		AC 2-Wire Mode	ls	AC/DC 2-Wire Models		
Model	Shield	led	Model	No.	Model	No.	Model	No.	Model	No.
		3 dia.			E2E-CR6□	1		·		
		4 dia.			E2E-CR8□	2				
Pre-wired Models		M5			E2E-X1□	4				
	Shielded	5.4 dia.			E2E-C1□	3				
	Silielded	M8	E2E-X2D	5	E2E-X1R5E□/F□	5	E2E-X1R5Y□	7		
		M12	E2E-X3D□	9	E2E-X2E□/F□	9	E2E-X2Y□	11	E2E-X3T1	13
rie-wiled Models		M18	E2E-X7D□	14	E2E-X5E□/F□	14	E2E-X5Y□	14	E2E-X7T1	14
		M30	E2E-X10D□	16	E2E-X10E□/F□	16	E2E-X10Y□	16	E2E-X10T1	16
		M8	E2E-X4MD□	6	E2E-X2ME□/F□	6	E2E-X2MY□	8		
	Unshielded	M12	E2E-X8MD□	10	E2E-X5ME□/F□	10	E2E-X5MY□	12		
	Offshielded	M18	E2E-X14MD□	15	E2E-X10ME□/F□	15	E2E-X10MY□	15		
		M30	E2E-X20MD□	17	E2E-X18ME□/F□	17	E2E-X18MY□	17	<del>-</del>	
	Shielded	M8	E2E-X2D□-M1(G)	18	E2E-X1R5E/F□-M1	18				
		M12	E2E-X3D□-M1(G)	20	E2E-X2E/F□-M1	20	E2E-X2Y□-M1	22		
		M18	E2E-X7D□-M1(G)	24	E2E-X5E/F□-M1	24	E2E-X5Y□-M1	24		
Connector Models		M30	E2E-X10D□-M1(G)	26	E2E-X10E/F□-M1	26	E2E-X10Y□-M1	26	<del>-</del>	
(M12)	Unshielded	M8	E2E-X4MD□-M1(G)	19	E2E-X2ME/F□-M1	19		ı		
,		M12	E2E-X8MD□-M1(G)	21	E2E-X5ME/F□-M1	21	E2E-X5MY□-M1	23		
		M18	E2E-X14MD□-M1(G)	25	E2E-X10ME/F□-M1	25	E2E-X10MY□-M1	25	<del></del>	
		M30	E2E-X20MD□-M1(G)	27	E2E-X18ME/F□-M1	27	E2E-X18MY□-M1	27		
Connector	Shielded		E2E-X2D□-M3G	28	E2E-X1R5E/F□-M3	28		ı		
Models (M8)	Unshielded	M8	E2E-X4MD□-M3G	29	E2E-X2ME/F□-M3	29				
		M8	E2E-X2D□-M1(T)GJ(-U)	30						
	01:-14-4	M12	E2E-X3D□-M1(T)GJ(-U)	31						
Pre-wired	Shielded	M18	E2E-X7D□-M1(T)GJ(-U)	33						
Connector		M30	E2E-X10D□-M1(T)GJ(-U)	35						
Models		M12	E2E-X8MD1-M1(T)GJ	32						
	Unshielded	M18	E2E-X14MD1-M1(T)GJ	34						
		M30	E2E-X20MD1-M1(T)GJ	36						
Pre-wired		M12	E2E-X3D1-M1J-T	31						
Connector Models	Shielded	M18	E2E-X7D□-M1J-T	33						
(no polarity)		M30	E2E-X10D□-M1J-T	35						
		·	hed washer are provided wit				<u> </u>		1	


Note 1. Two clamping nuts and one toothed washer are provided with M8 to M30 Models.

2. The model numbers of M8 to M30 Pre-wired Models are laser-marked on the milled section and cable section. This does not apply, however, to models that end in -U.

# **Pre-wired Models (Shielded)**



#### Diagram 1 E2E-CR6B / CR6C



\*2.4-dia. vinyl-insulated round cable with 3 conductors (Conductor cross section: 0.08 mm², Insulator diameter: 0.7 mm)

# 

#### E2E-C1B /C1C Diagram 3



\*2.9-dia. vinyl-insulated round cable with 3 conductors (Conductor cross section: 0.14 mm², Insulator diameter: 0.9 mm), Standard length: 2 m Robotics Cable Models: 2.9-dia. vinyl-insulated round cable with 3 conductors (Conductor cross section: 0.15 mm², Insulator diameter: 1.05 mm), Standard length: 2 m The cable can be extended up to 100 m (separate metal conduit).

#### Diagram 2 E2E-CR8B / CR8C



\*2.9-dia. vinyl-insulated round cable with 3 conductors (Conductor cross section: 0.14 mm², Insulator diameter: 0.9 mm), Standard length: 2 m Robotics Cable Models: 2.9-dia. vinyl-insulated round cable with 3 conductors (Conductor cross section: 0.15 mm², Insulator diameter: 1.05 mm), Standard length: 2 m The cable can be extended up to 100 m (separate metal conduit).

# **Mounting Hole Dimensions**



Dimension	3 dia.	4 dia.	5.4 dia.
F (mm)	$3.3^{+0.3}_{0}$ dia.	$4.2^{+0.5}_{0}$ dia.	$5.7^{+0.5}_{0}$ dia.

**OMRON** 

## **Pre-wired Models** (Shielded)




# **Mounting Hole Dimensions**



Dimension	М5	М8	M12		
F (mm)	$5.5^{+0.5}_{0}$ dia.	$8.5^{+0.5}_{0}$ dia.	$12.5^{+0.5}_{0}$ dia.		

#### Diagram 4 E2E-X1B /X1C




\*2.9-dia. vinyl-insulated round cable with 3 conductors (Conductor cross section: 0.14 mm2, Insulator diameter: 0.9 mm), Standard length: 2 m Robotics Cable Models

2.9-dia. vinyl-insulated round cable with 3 conductors (Conductor cross section: 0.15 mm², Insulator diameter: 1.05 mm), Standard length: 2 m The cable can be extended up to 100 m (separate metal conduit).

#### **Pre-wired Models (Unshielded)**



#### Diagram 5 E2E-X2D E2E-X1R5E /F



Toothed washer

\*1. 4-dia. vinyl-insulated round cable with 2 conductors (Conductor cross section: 0.3 mm², Insulator diameter: 1.3 mm), Standard length: 2 m

4-dia. vinyl-insulated round cable with 3 conductors (Conductor cross section: 0.3 mm², Insulator diameter: 1.3 mm), Standard length: 2 m

Robotics Cable Models:

4-dia. vinyl-insulated round cable with 2 conductors (Conductor cross section: 0.3 mm², Insulator diameter: 1.27 mm), Standard length: 2 m

4-dia. vinyl-insulated round cable with 3 conductors (Conductor cross section: 0.3 mm², Insulator diameter: 1.27 mm), Standard length: 2 m

Models with Highly Oil-resistant Cables:

4-dia. polyurethane-insulated round cable with 2 conductors (Conductor cross section: 0.3 mm², Insulator diameter: 1.3 mm), Standard length: 2 m


The cable can be extended up to 200 m (separate metal conduit).

\*2. D1 Models: Operation indicator (red) and setting indicator (green), D2/E/F Models: Operation indicator (red)

The cable can be extended up to 200 m (separate metal conduit).

2. D1 Models: Operation indicator (red) and setting indicator (green), D2/E/F Models: Operation indicator (red)

#### Diagram 6 E2E-X4MD E2E-X2ME /F




\*1. 4-dia. vinyl-insulated round cable with 2 conductors (Conductor cross section: 0.3 mm², Insulator diameter: 1.3 mm), Standard length: 2 m
4-dia. vinyl-insulated round cable with 3 conductors (Conductor cross section: 0.3 mm², Insulator diameter: 1.3 mm), Standard length: 2 m
Robotics Cable Models:

4-dia. vinyl-insulated round cable with 2 conductors (Conductor cross section: 0.3 mm², Insulator diameter: 1.27 mm), Standard length: 2 m
4-dia. vinyl-insulated round cable with 3 conductors (Conductor cross section: 0.3 mm², Insulator diameter: 1.27 mm), Standard length: 2 m
4-dia. vinyl-insulated round cable with 3 conductors (Conductor cross section: 0.3 mm², Insulator diameter: 1.27 mm), Standard length: 2 m
4-dia. vinyl-insulated round cable with 3 conductors (Conductor cross section: 0.3 mm², Insulator diameter: 1.27 mm), Standard length: 2 m
4-dia. vinyl-insulated round cable with 3 conductors (Conductor cross section: 0.3 mm², Insulator diameter: 1.27 mm), Standard length: 2 m
4-dia. vinyl-insulated round cable with 3 conductors (Conductor cross section: 0.3 mm², Insulator diameter: 1.27 mm), Standard length: 2 m
4-dia. vinyl-insulated round cable with 3 conductors (Conductor cross section: 0.3 mm², Insulator diameter: 1.27 mm), Standard length: 2 m
4-dia. vinyl-insulated round cable with 3 conductors (Conductor cross section: 0.3 mm², Insulator diameter: 1.27 mm), Standard length: 2 m
4-dia. vinyl-insulated round cable with 3 conductors (Conductor cross section: 0.3 mm², Insulator diameter: 1.27 mm), Standard length: 2 m
4-dia. vinyl-insulated round cable with 3 conductors (Conductor cross section: 0.3 mm², Insulator diameter: 1.27 mm), Standard length: 2 m
4-dia. vinyl-insulated cross (Conductor cross section: 0.3 mm², Insulator diameter: 1.27 mm), Standard length: 2 m
4-dia. vinyl-insulated cross (Conductor cross section: 0.3 mm², Insulator diameter: 1.27 mm), Standard length: 2 m
4-dia. vinyl-insulated cross (Conductor cross section: 0.3 mm², Insulator diameter: 1.27 mm), Standard length: 2 m
4-dia. vinyl-insulated cross (Conductor cross section: 0.3 mm², Insulator diameter: 1.27 mm), Standard length: 2 m
4-diameter: 1.27 mm, Standard length: 1

mm), Standard length: 2 m
The cable can be extended up to 200 m (separate metal conduit).


\*2. D1 Models: Operation indicator (red) and setting indicator (green), D2/E/F Models: Operation indicator (red)

#### E2E-X1R5Y Diagram 7



# Two clamping nuts other 4-dia. vinyl-insulated round cable with 2 conductors (Conductor cross section: 0.3 mm², Insulator diameter: 1.3 mm), Standard length: 2 m The cable can be extended up to 200 m (separate metal conduit).

#### E2E-X2MY Diagram 8



#### Pre-wired e-CON Connector Models E2E-X3D Diagram 9 E2E-X2E /F 38 -33--10 Connector: Product code 37104-3163-000FL (Sumitomo 3M) Indicators \* 2 M12 × 1 Two clamping nuts Toothed washer


- \*1.4-dia. vinyl-insulated round cable with 2 conductors (Conductor cross section: 0.3 mm², Insulator diameter: 1.3 mm), Standard length: 2 m 4-dia. vinyl-insulated round cable with 3 conductors (Conductor cross section: 0.3 mm², Insulator diameter: 1.3 mm), Standard length: 2 m Robotics Cable Models: 4-dia. vinyl-insulated round cable with 2 conductors (Conductor cross section: 0.3 mm², Insulator diameter: 1.27 mm), Standard length: 2 m 4-dia. vinyl-insulated round cable with 3 conductors (Conductor cross section: 0.3 mm², Insulator diameter: 1.27 mm), Standard length: 2 m
- 4-dia. vinyl-insulated round cable with 3 conductors (Conductor cross section: 0.3 milit; insulator unameter. 1.27 mm), Standard length: 2 m

  Models with Highly Oil-resistant Cables:
  4-dia. polyurethane-insulated round cable with 2 conductors (Conductor cross section: 0.3 mm², Insulator diameter: 1.3 mm), Standard length: 2 m

  The cable can be extended (separate metal conduit) up to 200 m for the control output and up to 100 m for the

- diagnostic output.

  \*2. D1 Models: Operation indicator (red) and setting indicator (green), D2/E/F Models: Operation indicator (red)



- \*1. 4-dia. vinyl-insulated round cable with 2 conductors (Conductor cross section: 0.3 mm2, Insulator diameter:
- \*1.4-dia. vinyl-insulated round cable with 2 conductors (Conductor cross section: 0.3 mm²· Insulator diameter: 1.3 mm), Standard length: 2 m

  4-dia. vinyl-insulated round cable with 3 conductors (Conductor cross section: 0.3 mm², Insulator diameter: 1.3 mm), Standard length: 2 m

  Robotics Cable Models:

  4-dia. vinyl-insulated round cable with 2 conductors (Conductor cross section: 0.3 mm², Insulator diameter: 1.27 mm), Standard length: 2 m


  4-dia. vinyl-insulated round cable with 3 conductors (Conductor cross section: 0.3 mm², Insulator diameter: 1.27 mm), Standard length: 2 m

  The cable can be extended (separate metal conduit) up to 200 m for the control output and up to 100 m for the diagnostic output.


- diagnostic output.

  \*2. D1 Models: Operation indicator (red) and setting indicator (green), D2/E/F Models: Operation indicator (red)

### Diagram 11 E2E-X2Y□



## Diagram 12 E2E-X5MY□




#### **Pre-wired Models (Shielded)**

# **Mounting Hole Dimensions**



Dimension	М8	M12	M18	M30
F (mm)	$8.5^{+0.5}_{0}$ dia.	12.5 <sup>+0.5</sup> dia.	18.5 <sup>+0.5</sup> dia.	$30.5^{+0.5}_{0}$ dia.


# Diagram 13 E2E-X3T1



# **Pre-wired Models (Unshielded)**




# Diagram 14 E2E-X7D□/E2E-X5E□/F□ E2E-X5Y\(\subseteq\)/E2E-X7T1



- \*1. 6-dia. vinyl-insulated round cable with 2 conductors (Conductor cross section: 0.5 mm², Insulator diameter: 1.9 mm), Standard length: 2 m 6-dia. vinyl-insulated round cable with 3 conductors (Conductor cross section: 0.5 mm²,
- Insulator diameter: 1.9 mm), Standard length: 2 m

Models with Highly Oil-resistant Cables:
6-dia, polyurethane-insulated round cable with 2 conductors (Conductor cross section: 0.5 mm², Insulator diameter: 1.9 mm), Standard length: 2 m
The cable can be extended (separate metal conduit) up to 200 m for the control output and up to 100 m for the diagnostic output.
\*2. D1/T Models: Operation indicator (red), Setting indicator (green)
D2/E/F/Y Models: Operation indicator (red)

Diagram 15 E2E-X14MD□/E2E-X10ME□/F□




- Toothed washer \*1. 6-dia. vinyl-insulated round cable with 2 conductors (Conductor cross section: 0.5 mm²,
- Insulator diameter: 1.9 mm), Standard length: 2 m 6-dia. vinyl-insulated round cable with 3 conductors (Conductor cross section: 0.5 mm², Insulator diameter: 1.9 mm), Standard length: 2 m Robotics Cable Models:
- 6-dia. vinyl-insulated round cable with 2 conductors (Conductor cross section: 0.5 mm²,
- 6-dia. vinyl-insulated round cable with 2 conductors (Conductor cross section: 0.5 mm², Insulator diameter: 1.74 mm), Standard length: 2 m
  6-dia. vinyl-insulated round cable with 3 conductors (Conductor cross section: 0.5 mm², Insulator diameter: 1.74 mm), Standard length: 2 m
  The cable can be extended (separate metal conduit) up to 200 m for the control output and up to 100 m for the diagnostic output.

  \*2. D1/T Models: Operation indicator (red), Setting indicator (green)

D2/E/F/Y Models: Operation indicator (red)

## Diagram 16 E2E-X10D□/E2E-X10E□/F□ E2E-X10Y\( \subseteq /E2E-X10T1



\*1. 6-dia. vinyl-insulated round cable with 2 conductors (Conductor cross section: 0.5 mm²,


Insulator diameter: 1.9 mm), Standard length: 2 m 6-dia. vinyl-insulated round cable with 3 conductors (Conductor cross section: 0.5 mm², Insulator diameter: 1.9 mm), Standard length: 2 m Robotics Cable Models:

6-dia. vinyl-insulated round cable with 2 conductors (Conductor cross section: 0.5 mm²,

6-dia. vinyl-insulated round cable with 2 conductors (Conductor cross section: 0.5 mm², Insulator diameter: 1.74 mm), Standard length: 2 m 6-dia. vinyl-insulated round cable with 3 conductors (Conductor cross section: 0.5 mm², Insulator diameter: 1.74 mm), Standard length: 2 m Models with Highly Oil-resistant: 6-dia. polyurethane-insulated round cable with 2 conductors (Conductor cross section: 0.5 mm², Insulator diameter: 1.9 mm), Standard length: 2 m The cable can be extended (separate metal conduit) up to 200 m for the control output and up to 100 m for the diagnostic output.

\*2. D1/T Models: Operation indicator (red), Setting indicator (green) D2/E/F/Y Models: Operation indicator (red)

# Diagram 17 E2E-X20MD□/E2E-X18ME□/F□



\*1.6-dia. vinyl-insulated round cable with 2 conductors (Conductor cross section: 0.5 mm², Insulator diameter: 1.9 mm), Standard length: 2 m 6-dia. vinyl-insulated round cable with 3 conductors (Conductor cross section: 0.5 mm²,

Insulator diameter: 1.9 mm), Standard length: 2 m Robotics Cable Models:

6-dia. vinyl-insulated round cable with 2 conductors (Conductor cross section: 0.5 mm², Insulator diameter: 1.74 mm), Standard length: 2 m

fished distributions in 1.74 mm), standard length: 2 m 6-dia. vinyl-insulated round cable with 3 conductors (Conductor cross section: 0.5 mm², Insulator diameter: 1.74 mm), Standard length: 2 m The cable can be extended (separate metal conduit) up to 200 m for the control output

and up to 100 m for the diagnostic output.

\*2. D1/T Models: Operation indicator (red), Setting indicator (green)
D2/E/F/Y Models: Operation indicator (red)

# **M8 Connector Models** (Shielded)




# **M8 Connector Models** (Unshielded)




# Diagram 28 E2E-X2D□-M3G/E2E-X1R5E□-M3/X1RF□-M3





# Diagram 29 E2E-X4MD□-M3G/E2E-X2ME□-M3/X2MF□-M3



## **M12 Connector Models** (Shielded)




# **M12 Connector Models** (Unshielded)



## Diagram 18 E2E-X2D□-M1(G) E2E-X1R5E -M1/E2E-X1R5F -M1






\* D1 Models: Operation indicator (red), Setting indicator (green) D2/E/F Models: Operation indicator (red)

#### Diagram 19 E2E-X4MD -M1(G) E2E-X2ME -M1/E2E-X2MF -M1






\* D1 Models: Operation indicator (red) Setting indicator (green) D2/E/F Models: Operation indicator (red)


# Diagram 20 E2E-X3D□-M1(G) E2E-X2E□-M1/E2E-X2F□-M1





\* D1 Models: Operation indicator (red), Setting indicator (green) D2/E/F Models: Operation indicator (red)


# Diagram 21 E2E-X8MD□-M1(G) E2E-X5ME□-M1/E2E-X5MF□-M1



\* D1 Models: Operation indicator (red), Setting indicator (green) D2/E/F Models: Operation indicator (red)

# Diagram 22 E2E-X2Y□-M1





# Diagram 23 E2E-X5MY□-M1




Diagram 24 E2E-X7D□-M1(G)/E2E-X5E□-M1/X5F□-M1 E2E-X5Y□-M1






\* D1 Models: Operation indicator (red), Setting indicator (green) D2/E/Y Models: Operation indicator (red)


Diagram 25 E2E-X14MD□-M1(G)/E2E-X10ME□-M1

X10MF□-M1




\* D1 Models: Operation indicator (red), Setting indicator (green) D2/E/Y Models: Operation indicator (red)

# 



\* D1 Models: Operation indicator (red), Setting indicator (green) D2/E/Y Models: Operation indicator (red)

# Diagram 27 E2E-X20MD□-M1(G)/E2E-X18ME□-M1/ X18MF□-M1 E2E-X18MY□-M1



\* D1 Models: Operation indicator (red), Setting indicator (green) D2/E/Y Models: Operation indicator (red)

# **Mounting Hole Dimensions**



Dimensions	М8	M12	M18	M30
F (mm)	8.5 <sup>+0.5</sup> dia.	12.5 <sup>+0.5</sup> dia.	18.5 <sup>+0.5</sup> dia.	30.5 <sup>+0.5</sup> dia.

33

# **Pre-wired Connector Models (Shielded)**




# **Mounting Hole Dimensions**



Dimension	M12	M18	M30	
F (mm)	12.5 <sup>+0.5</sup> dia.	18.5 <sup>+0.5</sup> dia.	30.5 <sup>+0.5</sup> dia.	


Diagram 30 E2E-X2D□-M1TGJ-U \*3 E2E-X2D1-M1TGJ






- 3. No U suffix: 4-dia. Vinyl-insulated round cable
  U suffix: 4-dia. Polyurethane insulated round cable,
  Standard length: 300 mm
  22. D1 Models: Operation indicator (red), Setting indicator (green)
  D2 Models: Operation indicator (red)
  3. The connectors for M1TGJ models are XS5 Smartclick connectors.

Diagram 31 E2E-X3D□-M1GJ E2E-X3D1-M1J-T E2E-X3D□-M1TGJ-U \*3







- O sontin, "Fullar, In Justice Manager Standard length: 300 mm 

  "2. D1 Models: Operation indicator (red), Setting indicator (green) 
  D2 Models: Operation indicator (red) 
  "3. The connectors for M1TGJ models are XS5 Smartclick connectors.

Diagram 33 E2E-X7D□-M1GJ E2E-X7D□-M1J-T

E2E-X7D□-M1TGJ-U \*3 E2E-X7D1-M1TGJ







- U suffix: 6-dia. Polyurethane insulated round cable, Standard length: 300 mm
- 2. D1 Models: Operation indicator (red), Setting indicator (green)
  D2 Models: Operation indicator (red)
  3. The connectors for M1TGJ models are XS5 Smartclick connectors.

Diagram 35 E2E-X10D□-M1GJ

E2E-X10D□-M1J-T E2E-X10D -M1TGJ-U \*3

E2E-X10D1-M1TGJ





- 11. No U suthx: 6-dia. Vinyl-insulated round cable
  U suffix: 6-dia. Polyurethane insulated round cable,
  Standard length: 300 mm
  12. D1 Models: Operation indicator (red), Setting indicator (green)
  D2 Models: Operation indicator (red)
  13. The connectors for M1TGJ models are XS5 Smartclick connectors.

## **Pre-wired Connector Models (Unshielded)**

Diagram 32 E2E-X8MD1-M1GJ E2E-X8MD1-M1TGJ






Diagram 34 E2E-X14MD□-M1GJ E2E-X14MD1-M1TGJ








Diagram 36 E2E-X20MD1-M1GJ E2E-X20MD1-M1TGJ






# **Dimensions for Proximity Sensors with Sensor I/O Connectors**


# **Shielded Models**

Straight Connectors

L-shape Connectors

# **Unshielded Models**





# Dimensions with the XS2F Connected (Unit: mm)

Dimension Sensor diameter		L1	L2
M8		Approx. 75	Approx. 62
M12*	DC	Approx. 80	Approx. 67
WILE	AC	Approx. 85	Approx. 72
M18		Approx. 85	Approx. 72
M30		Approx. 90	Approx. 77

<sup>\*</sup> The overall length of the Sensor is different between AC and DC Models for Sensors with diameters of M12. This will change the dimension when the I/O Connector is connected.

# Dimensions with the XS3F Connected (Unit: mm)

Dimension Sensor diameter	L1	L2
M8	Approx. 65	Approx. 54

# **Accessories (Order Separately)**

## **Sensor I/O Connectors**

Refer to Introduction to Sensor I/O Connectors for details.

**Mounting Brackets Protective Covers Sputter Protective Covers** 

Refer to Y92 ☐ for details.

**OMRON** 

#### Read and Understand This Catalog

Please read and understand this catalog before purchasing the products. Please consult your OMRON representative if you have any questions or comments.

#### Warranty and Limitations of Liability

#### WARRANTY

OMRON's exclusive warranty is that the products are free from defects in materials and workmanship for a period of one year (or other period if specified) from date of sale by OMRON.

OMRON MAKES NO WARRANTY OR REPRESENTATION, EXPRESS OR IMPLIED, REGARDING NON-INFRINGEMENT, MERCHANTABILITY, OR FITNESS FOR PARTICULAR PURPOSE OF THE PRODUCTS. ANY BUYER OR USER ACKNOWLEDGES THAT THE BUYER OR USER ALONE HAS DETERMINED THAT THE PRODUCTS WILL SUITABLY MEET THE REQUIREMENTS OF THEIR INTENDED USE. OMRON DISCLAIMS ALL OTHER WARRANTIES, EXPRESS OR IMPLIED.

#### LIMITATIONS OF LIABILITY

OMRON SHALL NOT BE RESPONSIBLE FOR SPECIAL, INDIRECT, OR CONSEQUENTIAL DAMAGES, LOSS OF PROFITS OR COMMERCIAL LOSS IN ANY WAY CONNECTED WITH THE PRODUCTS, WHETHER SUCH CLAIM IS BASED ON CONTRACT, WARRANTY, NEGLIGENCE, OR STRICT LIABILITY

In no event shall the responsibility of OMRON for any act exceed the individual price of the product on which liability is asserted.

IN NO EVENT SHALL OMRON BE RESPONSIBLE FOR WARRANTY, REPAIR, OR OTHER CLAIMS REGARDING THE PRODUCTS UNLESS OMRON'S ANALYSIS CONFIRMS THAT THE PRODUCTS WERE PROPERLY HANDLED, STORED, INSTALLED, AND MAINTAINED AND NOT SUBJECT TO CONTAMINATION, ABUSE, MISUSE, OR INAPPROPRIATE MODIFICATION OR REPAIR.

# **Application Considerations**

#### **SUITABILITY FOR USE**

OMRON shall not be responsible for conformity with any standards, codes, or regulations that apply to the combination of products in the customer's application or use of the products.

At the customer's request, OMRON will provide applicable third party certification documents identifying ratings and limitations of use that apply to the products. This information by itself is not sufficient for a complete determination of the suitability of the products in combination with the end product, machine, system, or other application or use.

The following are some examples of applications for which particular attention must be given. This is not intended to be an exhaustive list of all possible uses of the products, nor is it intended to imply that the uses listed may be suitable for the products:

- · Outdoor use, uses involving potential chemical contamination or electrical interference, or conditions or uses not described in this catalog.
- Nuclear energy control systems, combustion systems, railroad systems, aviation systems, medical equipment, amusement machines, vehicles, safety equipment, and installations subject to separate industry or government regulations.
- Systems, machines, and equipment that could present a risk to life or property.

Please know and observe all prohibitions of use applicable to the products.

NEVER USE THE PRODUCTS FOR AN APPLICATION INVOLVING SERIOUS RISK TO LIFE OR PROPERTY WITHOUT ENSURING THAT THE SYSTEM AS A WHOLE HAS BEEN DESIGNED TO ADDRESS THE RISKS, AND THAT THE OMRON PRODUCTS ARE PROPERLY RATED AND INSTALLED FOR THE INTENDED USE WITHIN THE OVERALL EQUIPMENT OR SYSTEM.

# PROGRAMMABLE PRODUCTS

OMRON shall not be responsible for the user's programming of a programmable product, or any consequence thereof.

#### **Disclaimers**

#### **CHANGE IN SPECIFICATIONS**

Product specifications and accessories may be changed at any time based on improvements and other reasons.

It is our practice to change model numbers when published ratings or features are changed, or when significant construction changes are made. However, some specifications of the products may be changed without any notice. When in doubt, special model numbers may be assigned to fix or establish key specifications for your application on your request. Please consult with your OMRON representative at any time to confirm actual specifications of purchased products.

#### **DIMENSIONS AND WEIGHTS**

Dimensions and weights are nominal and are not to be used for manufacturing purposes, even when tolerances are shown.

#### PERFORMANCE DATA

Performance data given in this catalog is provided as a guide for the user in determining suitability and does not constitute a warranty. It may represent the result of OMRON's test conditions, and the users must correlate it to actual application requirements. Actual performance is subject to the OMRON Warranty and Limitations of Liability.

#### **ERRORS AND OMISSIONS**

The information in this document has been carefully checked and is believed to be accurate; however, no responsibility is assumed for clerical, typographical, or proofreading errors, or omissions.

2010.8

In the interest of product improvement, specifications are subject to change without notice.



# **ПОСТАВКА** ЭЛЕКТРОННЫХ КОМПОНЕНТОВ

Общество с ограниченной ответственностью «МосЧип» ИНН 7719860671 / КПП 771901001 Адрес: 105318, г.Москва, ул.Щербаковская д.3, офис 1107

# Данный компонент на территории Российской Федерации Вы можете приобрести в компании MosChip.

Для оперативного оформления запроса Вам необходимо перейти по данной ссылке:

# http://moschip.ru/get-element

Вы можете разместить у нас заказ для любого Вашего проекта, будь то серийное производство или разработка единичного прибора.

В нашем ассортименте представлены ведущие мировые производители активных и пассивных электронных компонентов.

Нашей специализацией является поставка электронной компонентной базы двойного назначения, продукции таких производителей как XILINX, Intel (ex.ALTERA), Vicor, Microchip, Texas Instruments, Analog Devices, Mini-Circuits, Amphenol, Glenair.

Сотрудничество с глобальными дистрибьюторами электронных компонентов, предоставляет возможность заказывать и получать с международных складов практически любой перечень компонентов в оптимальные для Вас сроки.

На всех этапах разработки и производства наши партнеры могут получить квалифицированную поддержку опытных инженеров.

Система менеджмента качества компании отвечает требованиям в соответствии с ГОСТ Р ИСО 9001, ГОСТ РВ 0015-002 и ЭС РД 009

# Офис по работе с юридическими лицами:

105318, г. Москва, ул. Щербаковская д. 3, офис 1107, 1118, ДЦ «Щербаковский»

Телефон: +7 495 668-12-70 (многоканальный)

Факс: +7 495 668-12-70 (доб.304)

E-mail: info@moschip.ru

Skype отдела продаж:

moschip.ru moschip.ru\_6 moschip.ru 4 moschip.ru 9